

# **MAINTENANCE MANUAL**

FOR

**GENERAL ELECTRIC** 

# MPI

PERSONAL RADIO 403-512 MHz, 2/4 WATTS






# TABLE OF CONTENTS

| COMBINATION NOMENCLATURE   | iii              |
|--|------------------|
| SPECIFICATIONS   | iv               |
| DESCRIPTION  | 1                |
| OPERATION  | 1                |
| CHARGERS   | 1                |
| BATTERY PACK REPLACEMENT   | 2                |
| CIRCUIT ANALYSIS  Transmitter  T/R Board  Receiver  Voltage Regulator and T/R Switches | 2<br>2<br>3<br>5 |
| DISASSEMBLY  | 5                |
| SERVICE SHEET  | 7                |
| TROUBLESHOOTING PROCEDURE  | 8                |
| TRANSMITTER ALIGNMENT PROCEDURE  | 9                |
| RECEIVER ALIGNMENT PROCEDURE   | 10               |
| MECHANICAL LAYOUT11  | l, 12            |
| OUTLINE DIAGRAM13  | 3,14             |
| SCHEMATIC DIAGRAM15  | 5-19             |
| PARTS LIST20   | )-24             |

# **COMBINATION NOMENCLATURE**

| DIGITS 1&2      | DIGIT 3                     | DIGIT 4                     | DIGIT 5                    | DIGIT 6            | DIGIT 7               | DIGIT 8                     | DIGIT 9              |
|-----------------|-----------------------------|-----------------------------|----------------------------|--------------------|-----------------------|-----------------------------|----------------------|
| Product<br>Code | Package                     | TX<br>Frequency<br>Range    | RX<br>Frequency<br>Range   | Channel<br>Spacing | RF<br>Power<br>Output | Max.<br>Channel<br>Capacity | Control              |
| <b>P5</b>       | Accessory<br>Cover<br>Local | <b>M</b><br>403-425<br>MHz  | 403-425<br>MHz             | <b>5</b><br>25 KHz | 5<br>1.7-3.8<br>Watts | <b>B</b> 2 Tx-2 Rx          | <b>E</b><br>Standard |
|                 | C<br>Local/<br>Remote       | <b>N</b><br>420-450<br>MHz  | <b>N</b><br>420-450<br>MHz |                    | 3.9-6.4<br>Watts      | 2 Tx-1 Rx                   |                      |
|                 |                             | <b>R</b><br>450-470<br>MHz  | <b>R</b><br>450-470<br>MHz |                    |                       | 1 Tx-2 Rx                   |                      |
|                 |                             | <b>\$</b><br>470-494<br>MHz | <b>M</b><br>470-494<br>MHz |                    |                       | RC4365A                     |                      |
|                 |                             | 489-512<br>MHz              | 489-512<br>MHz             |                    |                       |                             |                      |

# STRUCTURED OPTIONS



#### TYPICAL SPECIFICATIONS\* SYSTEM

FCC IDENTIFICATION NUMBER

2-WATT 4-WATT AXA9MZTR102A-450-470 MHz AXA9MZTR121A-450-470 MHz AXA9MZTR121B-470-494 MHz AXA9MZTR121C-489-512 MHz

FREQUENCY RANGE

403-512 MHz

BATTERY DRAIN (MAXIMUM)

Receiver Standby Rated Audio

15 milliamperes 150 milliamperes

Transmitter

800 milliamperes @ 7.5 Volts (2-Watt) 1250 milliamperes @ 10 Volts (4-Watt)

7.81 on 4-Watt

TEMPERATURE RANGE

-30°C (-22°F) to +60°C (140°F)

DIMENSIONS (EIA) LESS ACCESSORIES

(H X W X D)

7.11 x 2.59 x 1.46 inches (180.5 x 65.7 x 37.1 millimeters)

WEIGHT, WITH ANTENNA

2-Watt 455 grams (16 ounces) 4-Watt 492 grams (17.3 ounces)

BATTERY LIFE

MAXIMUM FREQUENCY SPREAD

RF OUTPUT IMPEDANCE

At 5% - 5% - 90% Duty Cycle At 2% - 8% - 90% Duty Cycle

2-Watt 8 hours 12 hours

4-Watt 6.5 hours 11 hours

#### TRANSMITTER

POWER OUTPUT 2 Watts/4 Watts FREQUENCY STABILITY 0.0005% CONDUCTED SPURIOUS
AND HARMONIC EMISSION -16 dBm RATED SYSTEM DEVIATION ±5 kHz FM HUM & NOISE Greater than 50 dB AUDIO FREQUENCY Frequency Response per EIA RS 316-B. Post limiter filter per CHARACTERISTICS FCC and EIA. DISTORTION Less than 5% (300 to 3000 Hz) DEVIATION SYMMETRY 1.0 kHz maximum

NO 1 dB 3 dB
DEGRADATION DEGRADATION DEGRADATION 7 MHz 9 MHz 10 MHz 50 ohms

#### RECEIVER

AUDIO OUTPUT (to 8.0 ohm speaker) 500 milliwatts (less than 5% distortion)

SENSITIVITY
12 dB SINAD
20 dB Quieting 0.35 uV 0.50 uV FREQUENCY STABILITY 0.0005%

SELECTIVITY
EIA Two-Signal Method -70 dB @ ±25 kHz

SPURIOUS RESPONSE INTERMODULATION

-65 dB

MODULATION ACCEPTANCE SQUELCH SENSITIVITY

±6.7 kHz <6 dB SINAD

FREQUENCY RESPONSE

EIA RS 316-B

NO DEGRADATION 3 dB 6 dB
DEGRADATION DEGRADATION MAXIMUM FREQUENCY SPREAD 2 MHz 6 MHz RF INPUT IMPEDANCE 50 ohms

These specifications are intended primarily for use of the serviceman. Refer to the appropriate Specifications Sheet for the complete specifications.

#### DESCRIPTION

General Electric MPI Personal radios are extremely compact, high performance two-way FM radios designed for operation in the 450-470 MHz range. The lightweight radio utilizes both discrete components and Integrated Circuit modules (IC's).

All operating controls except the Push-To-Talk (PTT) switch and frequency select switch are conveniently located on the top of the radio. The frequency select and PTT switches are located on the side of the radio. An earphone jack, located above the PTT switch, is used with an earphone to provide message privacy, or to permit the operator to receive messages in noisy locations.

In Local/Remote combinations, an external microphone jack is located next to the earphone jack. This permits the transmitter to be keyed and messages transmitted using the external microphone.

Power for the radio is supplied by a rechargeable nickel-cadmium battery pack that fits in the bottom front section of the case. The battery pack can be recharged either in or out of the radio.

Test Adaptor 4EX12A12 is available to provide audio connections for servicing the transmitter and receiver.


#### **OPERATION**

If the radio is equipped with an option switch, disable the option before adjusting the radio by placing the switch in the OFF or MONITOR position. After adjusting the radio, place the option switch back in the CG OR T99 position (See Figure 1).

#### ADJUSTING THE RADIO

### To Receive a Message:

 Turn the OFF-VOLUME control about half way to the right.



- Disable any option by placing the option control toggle switch (if present) in the OFF or MONI-TOR POSITION.
- 3. Turn the SQUELCH (SQ) control to the right as far as possible. A hissing sound will be heard from the speaker.
- 4. Adjust the VOLUME control until the hissing sound is easily heard but not annoyingly loud.
- 5. Turn the SQUELCH control slowly to the left until the hissing noise just stops. This adjustment is very important as it eliminates annoying noise when no one is calling you. It also determines how sensitive your radio will be to incoming calls.
- 6. In two-frequency units, select the proper frequency. You are now ready to receive messages from other radios in your system.

#### To Send a Message:

- Turn on the radio as directed in the "To Receive a Message" section.
- 2. In two-frequency units, select the proper frequency. Then listen to make sure that no one is using the channel.
- 3. Hold the radio so that the antenna is vertical. Then, press the Push-To-Talk (PTT) bar and speak directly into the microphone in a clear and distinctive voice. Always release the PTT bar as soon as you stop talking. You cannot receive messages while the PTT bar is pressed.

#### CHARGERS


Three battery chargers are available for recharging the Nickel-Cadmium battery pack. For specific instructions, refer to the applicable operating instruction or maintenance manual.



#### BATTERY PACK REPLACEMENT

To remove the battery pack from the radio:

- 1. Turn the radio OFF.
- Place thumb on bottom of battery pack and press battery pack to-ward the top of radio as shown.
- 3. Then push bottom of battery pack away from the radio.



- WARNING -

Do not dispose of battery packs or batteries by burning. To do so may cause an explosion.

#### OSCILLATOR CRYSTAL REPLACEMENT

Crystals Y1, Y2, Y4, and Y5 are plug-in types for ease of replacement. Note that one lead is grounded to the crystal can. This lead must be plugged into the socket which is connected to the ground plane of the Transmit/Receive Board.

### CIRCUIT ANALYSIS

### TRANSMITTER

The Transmitter is a crystal-controlled, frequency modulated transmitter for one- or two-frequency operation in the 450-470 MHz bands. The transmitter utilizes discrete components to provide a minimum RF power output of two watts. The transmitter consists of the following assemblies.

- Audio Board with the microphone amplifier/limiter, postlimiter filter and oscillator compensator circuits.
- Transmit/Receive (TR) Board -Oscillator, Multiplier stages, amplifier, driver and PA stages, TR switch, and low-pass filter.

All supply voltages for the transmitter are provided by the battery and the Regueator. The different transmitter voltages required are shown in the following chart:

| Voltage                  | Used For  |
|--------------------------|---|
| Continuous<br>7.5 Volts  | Post-limiter filter,<br>driver and PA circuits              |
| Switched TX<br>7.5 Volts | Multipliers, 1st am-<br>plifier, and driver<br>base voltage |
| Switched TX 5.4 Volts    | Mic amp/limiter, mi-<br>crophone and oscil-<br>lator        |
| Regulated<br>5.4 Volts   | Compensator and modu-<br>lator circuits                     |

References to symbol numbers mentioned in the following text are found on the Schematic Diagrams, Outline Diagrams and Parts List. A block diagram of the complete transmitter and receiver is shown in Figure 2.

#### AUDIO CIRCUITS

Audio from the microphone is applied to a 6 dB pre-emphasis network (R16, D1, C15 and C18) and then to amplifier-limiters Q3 and Q4. The output of Q4 is applied to the post-limiter filter consisting of Q6, Q7, Q8 and associated circuitry.

The output of the post-limiter filter is coupled through C30 and the modulation circuitry to transmitter oscillator Q15.

A compensator circuit (Q9 and R36 through R40) provides frequency compensation at low temperatures for the transmitter and receiver oscillators.

#### T/R BOARD

#### OSCILLATOR

The temperature compensating DC voltage and audio is applied to FM modulators D6 and D7 through MOD ADJ controls R67 and R73. The modulator varactor varies the transmit frequency at the audio rate applied from the audio board.

Q15, Y4, Y5 and associated circuitry comprise a Colpitts oscillator. The transmit oscillator is adjusted to the assigned operating frequency by L39 and L42. The oscillator output is applied to buffer Q14. Channel 1 or Channel 2 is selected by S2.




Figure 2 - Block Diagram

L37 in the collector circuit of Q15 is tuned to the second harmonic. L36 provides additional filtering before multiplier/buffer stages Q13 and Q14. Drive to the multiplier/buffer stages can be monitored at J10 (TP4).

#### MULTIPLIERS

The output of Q13 is tuned to the fourth harmonic by L34 and L35, and applied to the base of multiplier Q12.

The output of multiplier Q12 is tuned to the eighth harmonic by C78 and C81. The emitter voltage of Q12 can be monitored at J9 (TP5).

#### AMPLIFIERS AND PA

Following Q12 is Class B amplifier Q11. Emitter voltage can be monitored at J8 (TP6). The output of Q11 is tuned by C70 to provide maximum drive to Q10. The output of Q10 is applied to the base of PA transistor Q9. C63 is tuned to provide impedance matching to the PA stage.

A collector feed network consisting of L19, L20, L24, L25, C57, C61, C66, C68, R44 and R47 acts as a stablizing and decoupling network for Q9 and Q10.

Power adjust control C56 is used to set the output power at two watts. The

PA output is applied to the antenna switch.

#### ANTENNA SWITCH

The solid state antenna switch consists of A1-D1, C1, C2, L1 and D1 on the TR board. The circuit acts as a 1/4-wave line simulator.

Keying the transmitter applies approximately 1.6 volts to the anode of A1-D1, forward biasing the diode. When A1-D1 is forward biased, the 1/4-wave line appears as an open circuit to the RF output of the transmitter. This allows the transmitter output to be coupled through the low-pass filter to the antenna. L17, C102 and R43 provide bias and decoupling for the antenna switch.

The antenna switch acts as a 50-ohm line in the receiver mode (A1-D1 not forward biased).

#### RECEIVER

The receiver is a dual conversion, superheterodyne FM receiver designed for one or two-frequency operation in the 450-470 MHz frequency range. A regulated 5.4 volts is used for all receiver stages except for the audio PA IC, receiver RF amplifier and mixer which operate from the 7.5 volt battery.

The receiver has intermediate frequencies of 21.4 MHz and 455 kHz. Adjacent channel selectivity is obtained by using three band-pass filters: (2) 21.4 MHz two-pole crystal filters and a 455 kHz ceramic filter.

All of the receiver circuitry except the audio PA and oscillator compensator is mounted on the transmitter/receiver (TR) board. The receiver consists of:

- Receiver Front End
- 21.4 MHz 1st IF circuitry
- 1st and 2nd Oscillators
- 455 kHz 2nd IF circuitry with FM Detector
- Audio PA Circuitry
- Squelch Circuitry

#### RECEIVER FRONT END

An RF signal from the antenna is coupled through the low-pass filter, antenna switch, and image filter to the emitter of RF amplifier Q1. The image filter consists of C3, C4, C5, C108 and L2.

The output of Q1 is coupled through two tuned circuits that provide most of the front end selectivity. The tuned circuits are L3, R4, C8 and C9, L4 and L5.

### OSCILLATOR AND MULTIPLIER

Q3, Y1, D2 and associated circuitry make up a Colpitts oscillator. The frequency is controlled by a third mode crystal operated at one ninth of the required injection frequency. Voltage-variable capacitor D2, L48 and Y1 are connected in series to provide compensation capability. The compensation voltage used to control the transmitter oscillators is applied to D2 to maintain stability. L48 is adjustable to set the oscillator frequency. R8 is in parallel with Y1 to insure operation on the third overtone of the crystal.

The oscillator output is coupled through two tuned circuits (L12-C25 and L13) to the base of tripler Q4. C25 and L13 are tuned to the third harmonic of the oscillator frequency. The output of tripler Q4 is coupled to the gate of first mixer Q2 through two tuned circuits (L14 and L15). L14 and L15 are tuned to the operating frequency minus 21.4 MHz which is the ninth multiple of the crystal frequency.

The DC level of the oscillator can be monitored at J6 (TP1). The meter reading at this point is typically 5.2 volts. The DC level of tripler Q4 can be measured at J7 (TP2). This meter reading is typically 5.2 volts.

#### 1ST MIXER AND IF FILTER

The 1st mixer uses a FET (Q2) as the active device. The FET mixer provides a high input impedance, high power gain and an output relatively free of intermodulation products).

In the mixer RF from the front end filter is applied to the gate of the mixer. Injection voltage from the multiplier stages is also applied to the gate of the mixer. The 21.4 MHz mixer 1st IF output signal is coupled from the drain of Q2 to crystal filters Z1 and Z2. Tuneable capacitor C12 is used to match the mixer obutput to the input of Z1.

The highly-selective crystal filter provides the first portion of the receiver IF selectivity. The output of the filter is coupled through R20 to the 1st IF amplifier.

Supply voltage for the RF amplifier and 1st mixer can be metered at J5 (TP3). The meter reading is typically 7.4 volts.

#### 1ST AND 2ND IF AND DETECTOR STAGES

The 21.4 MHz IF output of the crystal filters is applied to the base of IF amplifier Q5. The amplifier provides approximately 12 dB of IF gain. The output of Q5 is coupled through C35 to the input of the 2nd Mixer IC.

U1A and associated circuitry consists of the 2nd oscillator and mixer. The crystal for the oscillator is Y3. The oscillator operates at 20.945 MHz for low side injection of the 2nd IF (standard), or 21.855 MHz for high side injection for those radios determined to be operating on a tweet frequency. This frequency is mixed with the 21.4 MHz input to provide the 455 kHz 2nd IF frequency.

The output of U1A is coupled through ceramic filter Z3 which provides the 455 kHz selectivity. The filter output is applied to U1B.

U1B and associated circuitry consists of an IF amplifier, 455 kHz limiter and a quadrature type FM detector. L10 is the quadrature detector coil. Volume control R38 is used to set the audio output level to the audio amplifier. R37 and C48 provide a low pass filter to remove 455 kHz from the audio.

#### AUDIO AND SQUELCH CIRCUITS

#### Audio

Audio from the VOLUME arm is coupled through a twin-T Channel Guard notch filter that consists of Q1 and associated circuitry. The filter attenuates any audio frequency below 211 Hz.

The audio output from the filter is coupled through receiver muting switch Q10 to audio amplifier U1. Q10 is turned on in the receive mode to pass the audio. The 500 milliwatt audio output of U1 is coupled through C10 to the speaker and earphone jack.

A 6 dB/octave de-emphasis is provided by C12, C34, C6 and R10 in the audio feedback path. R7 and C5 provide additional de-emphasis at higher frequencies.

#### Squelch

The squelch circuit operates on the noise components contained in the FM detector output. The output of U1B is applied to a high-pass filter consisting of U1C, and associated circuitry. The output of U1C is noise in a band around 8 kHz.

With no RF signal present, the noise is rectified by D4 and a negative voltage is applied to the input of U1D, keeping it turned off and the receiver muted.

Pressing the PTT switch also forward biases clamping diode D5, keeping U1D input bias at the correct standby voltage in the transmit mode.

### RECEIVER SWITCH

Releasing the PTT switch turns off the transmitter switches and turns on receiver switch Q16. This applies 5.4 volts to the receiver oscillators, IF amplifier, audio and squelch stages.

#### DISASSEMBLY

To remove the front cover for servicing, first remove the battery. Then remove the two screws at A and lift off the front cover (See Figure 3).

To gain access to the back of the TR board, remove the two screws at  $\mbox{\ A}$  and the screw at  $\mbox{\ B}$  and remove the front and back covers.



Figure 3 - Disassembly

When an RF signal is received (receiver unsquelches), no noise is rectified by D4 and the input voltage at pin 12 of U1D rises to approximately +1 volt. This positive voltage turns on U1D, causing the output at U1D-14 to go positive, turning on buffer Q6. When turned on, the collector voltage of Q6 goes low, turning on PNP audio board squelch switch Q2. Turning on Q2 applies 7.5 volts to audio amplifier U1. This turns on U1 so that audio is heard at the speaker.

#### VOLTAGE REGULATOR AND TR SWITCHES

Turning off-on switch to the "on" position applies 7.5 volts to voltage regulator U2. The regulator output is set for 5.4 volts by regulator adjust control R40.

#### TRANSMITTER SWITCHES

Pressing the PTT switch turns on Q7 and Q8. When Q7 is turned on, 7.5 volts from the battery is applied to the transmitter multipliers and 1st amplifier stages. The 7.5 volts is also applied to the gate of receiver muting FET Q10. The positive voltage on the gate turns Q10 off and mutes the receiver in the transmit mode. The switched 7.5 volts is also applied to the base of RX 5.4 volt switch Q16, turning the switch off in the transmit mode.

— CAUTION —

Due to the excellent "drive" capability of the miniature TORX®-head screws, it is relatively easy to overtorque and damage the screws. The torque required for the screws is as follows:

- 1. 4 inch-pounds for the three M2.5 screws in the back cover.
- 2. 2 1/4 inch-pounds for the three M2 screws holding the accessory area cover plate (under the battery).

DO NOT OVERTORQUE!

If the radio is equipped with an option board, in addition to the above steps, the three screws holding the option cover must be removed.

| NO | Т | Ε |
|----|---|---|
|----|---|---|

The option board must be slightly raised to clear the option cover mounting boss before removing the back cover.

---- CAUTION ----

Do <u>not</u> bend the thin option board material any more than necessary.

GENERAL ELECTRIC COMPANY • MOBILE COMMUNICATIONS DIVISION WORLD HEADQUARTERS • LYNCHBURG, VIRGINIA 24502 U.S.A.



#### REPLACING CHIP COMPONENTS

Replacement of chip capacitors should always be done with a temperature-controlled soldering iron, using a controlled temperature of 700°F (371°C). However, do NOT touch black metal flim of the resistors or the ceramic body of capacitors with the soldering iron.

- NOTE -

The metalized end terminations of the parts may be touched with the soldering iron without causing damage.

#### REMOVING CHIP COMPONENTS

- Grip the component with tweezers or needle nose pliers.
- 2. Alternately heat each end of the chip in rapid succession until solder flows, and then remove and discard the chip.
- 3. Remove excess solder with a vacuum solder extractor or Solder-wick®.
- 4. Carefully remove the epoxy adhesive and excess flux to prevent damage to the printed board.

#### REPLACING CHIP COMPONENTS

- Using as little solder as possible, "tin" one end of the component and one of the pads on the printed wiring board.
- 2. Place the "tinned" end of the component on the "tinned" pad on the board and simultaneously touch the component and the pad with a well "tinned" soldering iron while pressing the component down on the board.
- 3. Place the "tinned" soldering iron on the other end of the component and the pad simultaneously. Apply solder to the top of the end of the component until the solder starts to flow. Use as little solder as possible while getting a good joint.
- 4. After the component has cooled, remove all flux from the component and printed wiring board area with alcohol.

#### HOLE CHART

| HOLE | DESCRIPTION                         |  |  |  |
|------|-------------------------------------|--|--|--|
| 1    | PTT SWITCH GND                      |  |  |  |
| 2    | OPT. GND                            |  |  |  |
| 3    | OPT. SW. GND                        |  |  |  |
| 4    | OPT. +7.5V                          |  |  |  |
| 5    | PTT FROM OPT.                       |  |  |  |
| 6    | OPT. +5.4V REG.                     |  |  |  |
| 7    | DISCRIMINATOR OUTPUT                |  |  |  |
| 8    | OPT. MUTE                           |  |  |  |
| 9    | PTT OUTPUT TO OPTIONS               |  |  |  |
| 10   | PTT SWITCH (HOT)                    |  |  |  |
| 11   | CG TONE INPUT TO XMTR               |  |  |  |
| 12   | FROM OPT. TO OPT. SW. CONN.         |  |  |  |
| 13   | FROM OPT. SW. TO OPT. CONN.         |  |  |  |
| 14   | PTT OUTPUT FROM OPTIONS             |  |  |  |
| 15   | SQUELCH FROM OPTIONS                |  |  |  |
| 16   | TX +7.5V                            |  |  |  |
| 0    |                                     |  |  |  |
| 18   | JUMPER WIRE                         |  |  |  |
| 19   | <i>S</i>                            |  |  |  |
| 20   | GND. FOR RF CHOKE                   |  |  |  |
| 21   | OPTION SW GND FOR MIN LO VOL OPTION |  |  |  |

#### TEST POINT CHART

| TP | FUNCTION        | TYP. V |
|----|-----------------|--------|
| 1  | RX INJ TUNING   | 5.2    |
| 2  | RX INJ TUNING   | 5.2    |
| 3  | RX INJ TUNING   | 7.4    |
| 4  | TX DRIVE TUNING | 0.4    |
| 5  | TX DRIVE TUNING | 0.6    |
| 6  | TX DRIVE TUNING | 0.8    |
| 7  | BATTERY INPUT   | 7.5    |
| 8  | GROUND          | 0      |

LBI31302

4EX12A12 - Personal Radio Test Set (Does not include any interconnect cables)

SERVICE TOOLS

Option 2847 - Internal J4 Interconnect Cable (May be used with any MPI radio)

Option 4990 - External Audio Jacks Interconnect Cable (Only used on units with remote mic capability)

Option 4120 - (Replaced TS 10 Service Tool Kit)

ST 2513 - Coil and Trim Pot Alignment Tool

ST 2521 - Oscillator Coil Alignment Tool

ST 2519 - Johanson Capacitor
Alignment Tool
(0.029" tip)

ST 2520 - Johanson Capacitor
Alignment Tool
(0.025" tip)

19A702672Pl - Battery Test Lead (Black)

19A702672P2 - Battery Test Lead (Red)

19B800747P3 - Audio Board Jumper

Cable (2 Required) 19A144745G1 - Receiver Audio Test Cable

19B800968G1 - RF Probe Assembly
Option 4121 - 7.5 Volt Dummy Battery Pack

(19D900773G1)
Option 4122 - 10 Volt Dummy Battery Pack

Option 4122 - 10 Volt Dummy Battery Pack (19D900773G2)

Mechanical Tools:

ST 2307 - Spanner wrench for audio

ST 2311 - Spanner wrench for vol-

ume & squelch controls
ST 0720 - Hex driver & assortment
of 8 TORX bits

SERVICE SHEET

Issue 1

| SYMPTOM                                  | PROCEDURE  |  |  |  |
|--|--|--|--|--|
| No 7.5V<br>Supply                        | Check power connections and continuity of supply leads, and check fuse. If fuse is blown, check radio for shorts.  |  |  |  |
| Low 7.5V<br>Supply                       | Check for low or uncharged battery possibly with bad cell.   |  |  |  |
| No 5.4V<br>Regulated<br>Supply           | Check the 7.5V supply at pin 4 of regulator U2. Then check adjustment of the voltage adjustment pot, R40. If a large standby current (i.e., >100 mA) is seen, check for a short to ground on the 5.4V output line.   |  |  |  |
| No Rx<br>5.4V                            | Check the 5.4V regulated supply. Then check switching transistor Q15.  |  |  |  |
| No Audio<br>Output                       | Check audio board squelching transistor, Q2. If the audio amplifier U1 is properly biased on, inject a 50 mV RMS, 1 kHz signal into the preceding stages until the faulty stage is isolated as follows. This signal must be capacitively coupled from the audio generator using a 1 uF electrolytic capacitor to avoid shifting bias voltages. Sequentially inject signal into the following points on the audio board: Pin 3 of U1, emitter of Q1, base of Q1, and P2-5 (volume control dependent). If the problem is not found on the audio board, check for recovered audio on the main board with an oscilloscope. Recovered audio should be seen at Pin 9 of U1, at Hole 7, and at Pin 3 of R38 (as well as the wiper depending upon position). |  |  |  |
| Low Audio                                | Measure supply voltage at Pin 6 of audio board IC (U1) and gate voltage of Q10. Verify that at least 150 mV (424 peak-to-peak) is present at Hole 7 when a strong RF signal is applied to the radio with standard test modulation. Check quad coil (L16) setting.  |  |  |  |
| Distorted<br>Audio Output                | Apply a strong RF signal with standard test modulation and measure audio distortion into an 8 ohm dummy load (e.g., test adaptor box). Distortion should be less than 5% at 2 volts output at 1 kHz. If there is low electrical distortion and acoustical distortion is still present, listen with test box or swap front covers with another radio to test speaker.   |  |  |  |
| No or<br>Incorrect<br>Detector<br>Output | Verify bias to Pins 4 and 8 of the main board IC, U1. Using a 50 ohm probe, inject a strong 21.4 MHz modulated signal into Pin 16 of U1. Recovered audio should be seen at Pin 9 and the level should vary with the setting of quad coil, L16. If none is seen, check the second oscillator for activity. At least 80 mV of RF should be seen on Pin 1 to ground.  |  |  |  |
| No 2nd<br>Oscillator<br>Activity         | Substitute a known good crystal for Y3. Check voltages on U1 pins 1 and 2.   |  |  |  |
| Radio<br>Permanently<br>Squelched        | Verify that main board IC, U1, is properly biased at Pins 4 and 8 and that quad coil L16 is correctly adjusted. The voltage at the Schmidt trigger input (U1 Pin 12) should rise and fall with the setting of R32. The output at pin 14 should switch bias on and off to the base of Q6 as the input threshold is crossed. The collector of Q6 should saturate and unsquelch the radio once the input (Pin 12) is above the threshold, approx. 0.8V.   |  |  |  |
| Radio Won't<br>Squelch                   | Verify that main board IC, U1, is properly biased at Pins 4 and 8 and that quad coil L16 is correctly adjusted. An oscilloscope should see high frequency (approx. 8 kHz) noise at the noise filter output, U1 pin 11. This noise should be seen at the wiper of R32 (dependent upon position) and should be negatively rectified by D4. The remainder of the squelch circuit is described under the "Radio Permanently Squelched" section.  |  |  |  |

# TROUBLESHOOTING PROCEDURE

Issue 1

| SYMPTOM   | PROCEDURE  |
|---|--|
| Poor or No<br>Sensitivity                                 | Verify that proper injection power is present and at the correct frequency, (f -21.4)/9. This can be done by 50 ohm probing from the junction of C33 and C103 to ground. The power seen should be approximately 0 dBm. If OK, then use the 50 ohm probe with a signal generator to inject signal into various portions of the radio to isolate the bad section. Set the generator with standard modulation to the level and frequency indicated on the large service schematic and probe those points starting with the IC (U1) and moving forward to the antenna jack. In some cases parts must be adjusted for best sensitivity while probing. This is indicated on the schematic. Once the faulty stage is isolated, measure bias voltages. |
| No or Low<br>Injection<br>Power                           | Verify that tuning procedure has been done or tried. The oscillator string can be trouble shot by using a 50 ohm probe connected to a power meter capable of measuring power as low as -20 dBm. Probe the available power points to ground indicated on the large service schematic. The power seen should be approximately that shown on the schematic. Any adjustment needed during probing is indicated on the schematic. Start probing with the oscillator and proceed towards the mixer. Bias voltages are also shown on the schematic for both a running and non-running oscillator. To kill a running oscillator, place a .01 uF ceramic capacitor with short leads from the base to collector of the oscillator transistor Q3.         |
| Frequency<br>Won't Adjust<br>Properly                     | Check compensator voltage at P3-2 and at varicap (D2, D6, D7 or D9). Check anode voltage of varicap.   |
| No Transmit<br>5.4V                                       | Check the switching transistor Q8.   |
| Radio Won't<br>Go Into<br>Transmit Mode                   | Verify that Hole 9 is going to ground when the PTT switch is pushed. If Channel Guard is present, first short Hole 9 and then Hole 5 to ground. Both operations should cause the radio to go into transmit mode unless a problem exists with the Channel Guard circuitry.  |
| Low or No<br>Transmit<br>Power                            | Check battery voltage when in transmit. Low or uncharged battery or shorted cell will be <7 volts. If the total transmit current is >500 mA, check the low pass filter and T/R switch. 1.6 VDC at C102 indicates that the radio is in the transmit mode. If the total transmit current is >100 mA, measure the base bias of Q10. Check for proper test point readings at TP4, TP5, TP6.  |
| Low TP6   | 0.5 - 0.8 VDC indicates proper drive into Q11. 0.3 VDC indicates no drive. Check the bias voltages.  |
| Low TP5   | 0.6 - 0.8 VDC indicates proper drive into Q12.<br>0 VDC indicates no drive. Check the bias voltages.   |
| High TP4  | 0.3 - 0.6 VDC indicates proper drive from the oscillator. With no oscillator activity TP4 will be 0.7 VDC.   |
| Oscillator<br>Frequency<br>Will Not<br>Adjust<br>Properly | Check the compensator voltage at P3-2. Check the anode voltage of the varicap.   |
| No Transmitter<br>Deviation                               | Disconnect the front cover and connect the test box. Apply 600 mV to TX audio. Check the DC and Audio Voltages on the Audio Board as indicated on the service schematic during transmit. If values are as indicated, substitute another front cover to test the microphone.  |

#### TRANSMITTER ALIGNMENT

#### EQUIPMENT REQUIRED

- 1. Power Supply (10 Volts, 2 Ampere).
- 2. 50 ohm Wattmeter with 50 ohm load
- 3. Audio Oscillator
- 4. Deviation Monitor
- 5. Frequency Counter
- 6. Voltmeter
- 7. Tune-up Kit TS10 (contains coil tuning tools, capacitor tuning tools, dummy battery, audio board jumper cables, and a 50 ohm probe).
- 8. Test adaptor 4EX12A12 and cable 19B234242G1 (Option 2847).


# PRELIMINARY STEPS AND ADJUSTMENTS

- 1. In addition to the antenna mounting bracket screw, the radio must be held tight against the back cover at the lower right corner near the negative battery terminal (e.g. use a 4-40 screw and nut).
- 2. Unplug the audio board and front cover from the main board.

- 3. Turn regulator output control R40 fully counterclockwise if voltage hasn't been previously adjusted. Insert the dummy battery into the battery pack area and apply nominal battery voltage (7.5 or 10 Volts as required) to the RED terminal (BLACK terminal is ground) on dummy battery pack.
- Connect multimeter to the output (Pin 5) of U2 (or J2-7) and ground, and adjust R40 for 5.4 Volts ±0.05 Volt. Try not to exceed 6 volts during adjustment.
- Pre-set the tuning slugs in L39 (and L42 in two-frequency radios) to the center of their tuning range.
- 6. All adjustments are made with the transmitter keyed and Channel Guard enabled, if present.

NOTE

In two-frequency radios, switch to the highest frequency.



ALIGNMENT PROCEDURE

| STEP | METERING<br>POINT    | TUNING<br>CONTROL | PROCEDURE   |
|------|----------------------|-------------------|---|
| 1.   | TP4                  | L37 and L36       | Adjust L37 and L36 in that order for a dip in meter reading.  |
| 2.   | TP5                  | L35 and L34       | Adjust L35 and L34 for a peak in meter reading. Repeat if necessary.  |
| 3.   | TP6                  | C81 and C78       | Adjust C81 and C78 in that order for a peak meter reading. Repeat if necessary.   |
| 4.   | Wattmeter            | C70, C63<br>C56   | Adjust C70, C63 and C56 in that order for maximum power output.   |
| 5.   | Wattmeter            | C56               | Turn C56 in the direction that causes both the power and current to decrease, and adjust C56 for an output of 2.0 Watts or 4.0 watts as applicable.  NOTE  The transmitter is designed to provide optional radiation efficiency (antenna matching) when the transmitter is adjusted for approximately rated power. Tuning for higher power will degrade both radiated power and battery life. |
|      |                      | FRE               | QUENCY ADJUSTMENT   |
| 6.   | Frequency<br>Counter | L39 and L42       | Plug the audio board onto the main board. In single frequency radios, adjust L39 for the proper frequency. In two frequency radios, switch to Channel 1 and adjust L39 for the proper frequency. Then switch to Channel 2 and adjust L42 for the proper frequency.  |
|      | <u> </u>             | MODU              | LATION ADJUSTMENT   |
| 7.   | Deviation<br>Monitor | R69 and R73       | Connect the test adaptor with cable to J4 and switch to channel 1. Apply 600 millivolts at 1 kHz to the test adaptor and adjust R69 for 4.5 kHz deviation. In twofrequency radios, switch to channel 2 and adjust R73 for 4.5 kHz deviation.  |

ALIGNMENT PROCEDURE

TRANSMITTER

LBI31302

#### RECEIVER ALIGNMENT

#### EQUIPMENT REQUIRED

- 1. 10-Volt Power Supply. (0.5 amps)
- Floating terminal (non-grounded) multimeter with at least 3 1/2 digits and a 200 millivolt DC lowest range.
- 3. RF generator.
- 4. Distortion analyzer.
- MPI Tune-up kit TS10 containing coil tuning tools, trimmer capacitor tuning tools, dummy battery, audio board jumper cables and a 50 ohm probe.
- 6. Test Adaptor 4EX12A12 and MPI Cable 19B234242G1 (Option 2849 for internal jack, or Option 4990 for jacks on side rail.

#### PRELIMINARY CHECKS AND ADJUSTMENTS

- 1. In addition to the antenna mounting bracket screw, the radio must be held tight against the back cover at the lower right corner near the negative battery terminal (e.g. use a 4-40 screw and nut).
- 2. Remove the front cover and unplug the Audio board from the

- main board. Then connect the audio board to the main board with the jumper cables.
- 3. Turn regulator output control R40 fully counterclockwise if voltage hasn't been previously adjusted. Insert the dummy battery into the battery pack area and apply nominal supply voltage (7.5 or 10 Volts as required). Volts to the RED terminal (BLACK terminal is ground) on dummy battery.
- 4. Connect multimeter to the output (Pin 5) of U2 (or J2-7) and ground, and adjust R40 for 5.4 Volts ±0.05 Volt. Try not to exceed 6 volts during adjustment.
- 5. Pre-set the tuning slugs in L3, L13, L14, L15, L48 and L49 to the top of the coil form. Next, set the arrow on the rotor of C12 and C25 so that it points towards the rounded end of the capacitor.
- 6. Disable Channel Guard, if present.

- NOTE -

In two-frequency radios, all adjustments are made on the lowest frequency except as directed.

#### ALIGNMENT PROCEDURE


| STEP | METERING<br>POINT                                   | TUNING<br>CONTROL                  | PROCEDURE   |
|------|---|------------------------------------|---|
| 1.   | Audio<br>Output<br>Jack<br>(J1 on<br>side<br>panel) | L16                                | Set the Volume Control an audio level of approximately 1 Volt RMS to keep out of limiting. Using the 50 ohm probe, apply a strong modulated 21.4 MHz signal (>-50 dBm) to U1A-16 on T/R board and adjust L16 for maximum audio output.  NOTE  If a 21.4 MHz generator is not available, adjust L16 for maximum noise. |
| 2.   | J2-7 and<br>TP1                                     | L48 (Chan 1)<br>or L49<br>(Chan 2) | For two frequency radios, select the lowest frequency. While measuring between J2-7 (regulator voltage) and TP1, adjust L48 or L49 for maximum meter reading (approximately 250 millivolts).  |
| 3.   | Audio<br>Output<br>Jack<br>(J1 on<br>side<br>panel) | C25, C9 and<br>L13                 | Apply a strong (0 dBm) signal to the antenna jack. Adjust C25, C9 and L13 for best quieting. C25 will have more than two dips, so use only the stronger one. Then adjust C25 and L13 again for best quieting.   |
| 4.   | Audio<br>Output<br>Jack<br>(J1 on<br>side<br>panel) | L14, L15, C4,<br>L3 and C9         | Adjust L14, L15, C4, L3 and C9 in that order for best quieting.   |

# ALIGNMENT PROCEDURE


RECEIVER

10 Issue 1

PROCEDURE TUNING STEP METERING POINT CONTROL Distortion L48, L49 Add 1 kHz tone modulation at 5 kHz deviation to the carrier. Leave the Volume control as Analyzer in Step 1. Alternately adjust lowest frequency warp coil (L48 or L49) and C12 until no improvement in SINAD is seen. This will insure that the match to the crystal filters is properly adjusted, and that the carrier is centered in the pass band (zero beating isn't required). On 2 frequency radios switch to the other channel and adjust the other warp coil (L48 or L49) for best SINAD. On two-frequency radios, switch to the Distortion lowest frequency. Set the signal generator to the image frequency (42.8 MHz below the Analyzer carrier frequency) and increase the RF level to approximately -60 dBm. Then adjust C4 for the amount of image rejection desired by degrading the quieting on SINAD. Then reset the signal generator to 3 kHz before doing any standard measurements.



(19D901015)



1 VHF SEE NOTES 4 5 8

2 UHF SEE NOTE 8

3 VHF - TWO FRED TX & SINGLE FRED RX SEE NOTES 4

UHF - TWO FREQ TX & SINGLE FREQ RX
SEE NOTE 6

5 DTMF SEE SH. #

6 VHF - SINGLE FREQ TX & TWO FREQ RX SEE NOTES

7 UHF - SINGLE FREQ TX 8 TWO FREQ RX SEE NOTE

#### NOTES:

1. ITEMS MARKED ■ ARE PART OF HARDWARE KIT PL19A702379G2 (UHF)
ITEMS MARKED ▲ ARE PART OF HARDWARE KIT PL19A702379G3 (VHF)

ROTATE OFF/ON-VOL POT TO EXTREME COUNTER CLOCKWISE (OFF) POSITION.
ASSEMBLE KNOB WITH INDICATOR MARK ALIGNED WITH MARK ON TOP COVER.
ROTATE SQUELCH POT TO EXTREME COUNTER CLOCKWISE POSITION. ASSEMBLE KNOB WITH INDICATOR MARK IN APPROXIMATELY SAME POSITION AS THE OFF/ON-VOL KNOB.

APPLY SILICON GREASE (19A701337P1MPPER 19A701431 BETWEEN MATING SURFACES OF HEAT SINK, NUT, TRANSISTOR AND REAR COVER. SCREW MUST BE TIGHTENED BEFORE NUT. NUT TIGHTENING TORQUE TO BE 0.6±0.1 N-M.

CUT RUNS ON SOLDER SIDE OF TX/RX BOARD 19D901016G1 WHEN LOWEST TX FREQ SPECIFIED IS BELOW 142 MHz OR ON TX/RX BOARD 19D901016G2 WHEN LOWEST TX FREQ SPECIFIED IS BELOW 162 MHz AS SHOWN IN DETAIL "G" (SH. #2).

when no TX CRYSTALS ARE SPECIFIED ON PRODUCTION TAG DO NOT CUT RUNS SHOWN IN DETAIL "G" (SH. #2).

 $\frac{\sqrt{6\lambda}}{\text{DETAIL "D"}}$  Cut run on solder side of TX/RX board and ADD jumpers as shown in Detail "D" (SH. #2).


CUT RUN ON SOLDER SIDE OF TX/RX BOARD AND ADD JUMPERS AS SHOWN IN DETAIL "E" (SH. #2).


8 REFER TO PRODUCTION TAG TO DETERMINE WHICH OF THE FOLLOWING APPLY


|   | OPTIONS   | INSTRUCTIONS  |
|---|---|---|
|   | A0.B0   | TX & RX CRYSTALS OMITTED  DO NOT REMOVE SWITCH STOP SHOWN IN DETAIL "C"(SH. #2)                     |
| İ | AA,BA   | SINGLE FREQ. TX & RX<br>  <u>DO NOT</u> REMOVE SWITCH STOP<br>  SHOWN IN DETAIL "C"(SH. #2)         |
|   | AB.BB   | TWO FREQ. TX & RX<br>  REMOVE SWITCH STOP SHOWN IN<br>  DETAIL "C" (SH. #2)                         |
|   | AA,BA<br>WITH ONE<br>OR MORE<br>FREQ'S<br>LISTED AS | TWO FREQ. TX & RX WITH ONE SET OF CRYSTALS OMITTED. REMOVE SWITCH STOP SHOWN IN DETAIL "C" (SH. #2) |


9. SOLDER ALL ELECTRICAL CONNECTIONS.


ORIENT Y1, Y2, Y4 AND Y5 SO THAT DWG. NO. 8 FREQ. MARKING IS AT SIDE INDICATED. GROUND LEAD MUST BE IN POSITION AS INDICATED BY (SH. #2)



















FRONT VIEW


(19D901015, Sh. 1, Rev. 1) (19A7033 5, Sh. 1, Rev. 1) (19A703305






QI & Q2 on Main Board on Audio Board








OUTLINE DIAGRAM

13

TRANSMITTER/RECEIVER BOARD

Issue 1



HT1 + HT2 + HT2 + HT3 + HT1 + HT2 + HT2 + HT3 + HT3 + HT2 + HT3 +

L16,L39,L42, L48 & L49 STANDARD OUTLINE TRANSISTORS (SOTS) TU U3 (TOP VIEW) (BOTTOM VIEW) MICROPHONE DIODES & VARACTORS TO - 92 (REAR VIEW) (BOTTOM VIEW) GD S R23 & R38 FET (BOTTOM VIEW) R40, R69 & R73 ( BOTTOM VIEW) BOARD


RC 4372B

FRONT SIDE

(19D901124, Rev. 0) (19A703568, Sh. 1, Rev. 0) (19A703568, Sh. 2, Rev. 0)

BACK SIDE

(19D901123, Rev. 1) (19A703568, Sh. 2, Rev. 0)



# OUTLINE DIAGRAM

AUDIO BOARD

14

Issue 1

# LBI31302

| FREQUENCY | SENSITIVE | COMPONENTS      |
|-----------|-----------|-----------------|
|           |           | 00111 011121110 |

|         |             |                 | STITVE COMPO    |             |                 |
|---------|-------------|-----------------|-----------------|-------------|-----------------|
| REF.    | G 1         | G2              | G3              | G4          | G <b>5</b>      |
| NO.     | 450-470 MHZ | 470-494 MHZ     | 489-512 MHZ     | 403-425 MHZ | 420-450 MHZ     |
| C1#     | 5.6P        | 5.6P            | 5.6P            | 6.8P        | 5.6P            |
|         |             |                 |                 |             |                 |
| C2#     | 6.8P        | 6.8P            | 3.9p            | 8.2P        | 6.8P            |
| C3#     | 2.7P        | 2.7P            | 2.7p            | 3.3p        | J.JP            |
| C4      | 0.5-2.5p    | 0.5-2.5p        | 0.5-2.5p        | 1-5p        | 1-5p            |
| C5#     | 2.7p        | 2.7p            | 2.7P            | 3.3p        | 3.3P            |
| C8#     | 1.2P        | 0.9p            | 0.5p            | 1.8=        | 1.8p            |
| C19#    | 100p        | 100p            | 100p            | 68P         | 150p            |
| C22     | 68p         | 68P             | 68P             | 120p        | 120p            |
| C23#    |             |                 |                 |             |                 |
|         | 22p         | 15p             | 15p             | 30p         | 24P             |
| C24#    | 3.3p        | 4.7p            | 4.7p            | 1.7P        | 4.7p            |
| C27#    | 15p         | 12p             | 13p             | 22P         | 8 P             |
| C30#    | 2.7P        | 1.8p            | 1.8P            | 3.3P        | 2.7p            |
| C32#    | 3.3P        | 2.7p            | 2.7P            | 4.3P        | 3.9p            |
| C54#    | 1 Op        | 8.2P            | 6.2P            | 12P         | 12p             |
| C55#    | 3.9P        | NONE            | NONE            | 8.2P        | 5.6P            |
| C58#    | 12p         | 10p             | 8.2P            | 15e         | 15p             |
| C59#    | 39P         | 36P             | 33P             | 47P         | 43P             |
| C60#    | 39P         | 36P             | 33P             | 47 <b>P</b> | 43P             |
|         |             |                 |                 |             |                 |
| C65#    | 12P         | 12P             | 12=             | 24P         | 22P             |
| C71#    | 10P         | 10p             | 8.2p            | 15P         | 10 <del>P</del> |
| C85#    | 39p         | 39₽             | 39p             | 43p         | 39p             |
| C86#    | 22P         | 22 <b>p</b>     | 22 <b>P</b>     | 24P         | 24P             |
| C87#    | 39p         | 33 <sub>P</sub> | 33p             | 51 P        | 43P             |
| C89#    | 10p         | 10p             | 8.2P            | 12p         | 12P             |
| C93#    | 39P         | 39p             | 39P             | 43P         | 39P             |
| C94#    | 18p         | 18p             | 18-             | 27P         | 22P             |
| C95#    | 47P         | 47P             | 47P             | 56P         | 47p             |
|         |             |                 |                 |             |                 |
| C96#    | 2.7p        | 2.7p            | 2.2P            | 3.3p        | 2.7P            |
| C97#    | ე∩ <b>թ</b> | 27 <b>P</b>     | 27 <b>P</b>     | 39P         | 36P             |
| C108    | €.8p        | 4.7p            | 4.7P            | 6,8P        | 6.8P            |
| C110#   | 10p         | 10P             | 8.2p            | 15p         | 10P             |
| L1      | 2 1/2 TURNS | 2 1/2 TURNS     | 2 1/2 TURNS     | 2 1/2 TURNS | 2 1/2 TURNS     |
| L.I     | 2.Omm ID    | 1.78mm ID       | 1.78mm ID       | 2.2mm ID    | 2.2mm ID        |
|         |             |                 | 2 1/2 TURNS     |             | 2 1/2 TURNS     |
| L4 & L5 | 2.Omm ID    | 2.0mm ID        | 1.78mm ID       | 2.0mm ID    | 2.0mm ID        |
| L7 & L8 | 1 u         | 10              | 1 1 U           | 1.20        | 1.2u            |
| L9      | 680n        | 680n            | 560n            |             |                 |
| L7      |             |                 |                 | 1 u         | 820n            |
| L11     | 3 1/2 TURNS | 4 I/ TURNS      | 4 1/2 TURNS     |             | 3 1/2 TURNS     |
|         | 3.04mm ID   | 3.04mm ID       | 3.04mm ID       | 3.04mm ID   | 3.04mm ID       |
| L12     | 150n        | 120n            | 120n            | 150n        | 150n            |
| L38     | 270n        | 270n            | 220n            | 470n        | 390n            |
| L44     | 1 1/2 TURNS | 1 1/2 TURNS     | 1 1/2 TURNS     | 1 1/2 TURNS | 1 1/2 TURNS     |
| L+4     | 2.Omm ID    | 1.52mm ID       | 1.52mm ID       | 2.0mm ID    | 2.0mm ID        |
|         | ر 3/4 TURNS |                 |                 | 3 3/4 TURNS |                 |
| L45     | 2.54mm ID   | 2.54mm ID       | 2.03mm ID       | 2.54mm ID   | 2.54mm ID       |
| R4#     | 2.7k        | 2.2k            | 2.2k            | 3.3k        | 3.3k            |
| R10#    |             |                 |                 |             |                 |
|         | 120         | 20              | 120             | 180         | 180             |
| R11     | 120         | 120             | 120             | 180         | 180             |
| R15#    | 560         | 560             | 560             | 390         | 390             |
| R77#    | 22k         | 22k             | <sup>7</sup> 2k | 1 8 k       | 18k             |
| R78#    | 68k         | 68k             | 68k             | 82k         | 82k             |
| R79#    | 47k         | 47k             | 47k             | 27k         | 27k             |
| R80#    | 82k         | 82k             | 82k             | 100k        | 100k            |
|         |             |                 |                 |             |                 |
|         |             |                 |                 |             |                 |

#### VOLTAGE READINGS:

VOLIAGE PEADINGS ARE TYPICAL VALUES MEASURED WITH A HIGH IMPEDANCE (@@:10M\alpha) MUL.I-METFR FROM THE INDICATED POINT TO GROUND. CONDITIONS FOR PEADINGS ARE INDICATED BY THE FOLLOWING KEY:

- R INDICATES VOLTAGES ARE TO BE MEASURED DURING RECEIVE MODE
  T INDICATES MEASUREMENT DURING TRANSMIT C INDICATES CONTINUOUS VOLTAGE ALWAYS PRESENT WHEN RADIO IS ON

VOLTAGE READINGS ARE FOR 4 WATT MPI UNITS UNLESS ENCLOSED IN BRACKETS WHICH INDICATES VOLTAGES MEASURED ON 2 WATT MPI UNITS. (EXAMPLE: [+7.5V])

#### NOTES

(19D901014, Sh. 1, Rev. 1)

A PART OF PWB.

- 3. # IDENTIFIES "CHIP" COMPONENTS (EXAMPLE C57#)
  WHICH ARE LOCATED ON SOLDER SIDE OF PWB.
- 4. † FREQUENCY SENSITIVE COMPONENTS, SEE COMPONENT IDENTIFICATION CHART OR PARTS LIST. G1 PART VALUE SHOWN.
- 5. ALL CHIP RESISTORS ARE 1/0 WATT.
  ALL OTHER RESISTORS ARE 1/0 WATT UNLESS OTHERWISE SPECIFIED.
  RESISTOR VALUES IN \( \Omega\$ UNLESS FOLLOWED BY MULTIPLIER k OR M.
  CAPACITOR VALUES IN F UNLESS FOLLOWED BY MULTIPLIER u,n OR P.
  INDUCTANCE VALUES IN H UNLESS FOLLOWED BY MULTIPLIER m,u OR n.

& CUT THIS RUN FOR CG/CCT OPTION.


| DESCRIPTION                      | MODEL NO.     | REV LTR |
|----------------------------------|---------------|---------|
| UHF 2W/4W MAIN BD 450-470 MHZ    | PL19D901012G1 |         |
| UHF 2W/4W MAIN BD 470-494 MHZ    | PL19D901012G2 |         |
| UHF 2W/4W MAIN BD 489-512 MHZ    | PL19D901012G3 |         |
| UHF 2W/4W MAIN BD 403-425 MHZ    | PL19D901012G4 |         |
| UHF 2W/4W MAIN BD 420-450 MHZ    | PL19D901012G5 |         |
| AUDIO BOARD (STANDARD)           | PL19D901123G1 |         |
| AUDIO BOARD (W/DTMF PARTS)       | PL19D901123G2 |         |
| BATTERY (7.5V)                   | PL19D900639G2 |         |
| BATTERY (10V)                    | PL19D900639G3 |         |
| REAR COVER (2 WATT)              | PL19D901087G4 |         |
| REAR COVER (4 WATT)              | PL19D901087G2 |         |
| SIDE PANEL                       | PL19D901089G1 |         |
| FRONT COVER (STANDARD)           | PL19D900647G1 |         |
| FRONT COVER (LICENSEE)           | PL19D900647G2 |         |
| FRONT COVER (STANDARD W/O METAL) | PL19D900647G4 |         |
| FRONT COVER (STANDARD/DTMF)      | PL19D901011G1 |         |
| FRONT COVER (LICENSEE/DTMF)      | PL19D901011G2 |         |

SCHEMATIC DIAGRAM

Sheet 1


15


Issue l



SCHEMATIC DIAGRAM

403-512 MHz RX Sheet 2 16 Issue 1 RC4427 SH.2






(19D901014, Sh. 4, Rev. 0)

RC4427 SH.

# SCHEMATIC DIAGRAM



(19D901014, Sh. 5, Rev. 1)

SCHEMATIC DIAGRAM

# PARTS LIST

2/4 WATT TRANSMIT/RECEIVE BOARD
19D901012G1 450-470 MHz
19D901012G2 470-494 MHz
19D901012G3 489-512 MHz
19D901012G4 403-425 MHz
19D901012G5 420-450 MHz
ISSUE 1

| SYMBOL            | GE PART NO.   | DESCRIPTION  |
|-------------------|---------------|--|
| A 1               |               | FILTER BOARD<br>19B801039G1  |
|                   |               |  |
| C1                | 19A700219P14  |  |
| C2                | 19A700219P40  | Ceramic: 22 pF ±10%, 100 VDCW, temp coef 0 PPM.  |
| СЗ                | 19A700219P12  | Ceramic: 2.7 pF ±5%, 100 VDCW, NPO.  |
| C4                | 19A700219P20  | Ceramic: 5.6 pF ±5%, 100 VDCW, temp coef 0 PPM.  |
|                   |               |  |
| D1                | 19A702411P1   | Silicon; sim to Hewlett Packard 5082-3188.   |
|                   |               | INDUCTORS  |
| L1                | 19A702472P3   | Coil.  |
| L2                | 19A702472P1   | Coil.  |
|                   |               |  |
| C1                | 19A702061P11  | Ceramic: 6.8 pF ±0.5 pF, 50 VDCW, temp coef 0<br>±60 PPM. (Used in G4).                  |
| C1                | 19A702061P10  | Ceramic: 5.6 pF ±0.5 pF, 50 VDCW, temp coef 0 ±60 PPM. (Used in G1-G3, G5).              |
| C2                | 19A702061P11  | Ceramic: 6.8 pF $\pm$ 0.5 pF, 50 VDCW, temp coef 0 $\pm$ 60 PPM. (Used in G1, G2, G5).   |
| C2                | 19A702061P12  | Ceramic: 8.2 pF $\pm$ 0.5 pF, 50 VDCW, temp coef 0 $\pm$ 60 PPM. (Used in G4).           |
| C2                | 19A702061P908 | Ceramic: 3.9 pF ±.25 pF, 50 VDCW, temp coef 0<br>±120 PPM. (Used in G3).                 |
| сз                | 19A702061P906 | Ceramic: 2.7 pF $\pm$ .25 pF, 50 VDCW, temp coef 0 $\pm$ 120 PPM. (Used in G1-G3).       |
| СЗ                | 19A702061P907 | Ceramic: 3.3 pF +.25 pF, 50 VDCW, temp coef 0 +120 PPM. (Used in G4 & G5).               |
| C4                | 19B800873P7   | Variable, ceramic: 0.5 to 2.5 pF, 150 VDCW; sim to Johanson 9620. (Used in G1-G3).       |
| C4                | 19B800873P8   | Variable, ceramic: 1 to 5 pF, 150 VDCW; sim to<br>Johanson 9621. (Used in G4 & G5).      |
| C5                | 19A702061P906 | Ceramic: 2.7 pF +.25 pF, 50 VDCW, temp coef 0 +120 PPM. (Used in G1-G3).                 |
| <b>C</b> 5        | 19A702061P907 | Ceramic: 3.3 pF ± .25 pF, 50 VDCW, temp coef 0 +120 PPM. (Used in G4 & G5).              |
| C6<br>and         | 19A702061P69  | Ceramic: 220 pF ±5%, 50 VDCW, temp coef 0 ±30 PPM.                                       |
| C7<br>C8          | 19A702061P902 | Ceramic: 1.2 pF ±.25 pF, 50 VDCW, 0 ±250 PPM.  |
| C8                | 19A702236P5   | (Used in G1).  Ceramic: 0.9 pF ±.1 pF, 50 VDCW, 0 ±30 PPM.                               |
| C8                | 19A702236P1   | (Used in G2).  Ceramic: 0.5 pF ±.1 pF, 50 VDCW, temp coef                                |
| C8                | 19A702061P904 | $0 \pm 30$ PPM. (Used in G3).<br>Ceramic: 1.8 pF $\pm .25$ pF, 50 VDCW, $0 \pm 250$ PPM. |
| С9                | 19B800873P8   | (Used in G4 & G5).  Variable, ceramic: 1 to 5 pF, 150 VDCW; sim to                       |
| C10<br>and<br>C11 | 19A702052P14  | Johanson 9621.  Ceramic: $0.01 \text{ uF } \pm 10\%$ , 50 VDCW.                          |
| C12               | 19A702168P4   | Variable, cerramic: 5.2 to 30 pF, 100 VDCW, tem coef N750+300 PPM; sim to JFD DV2SN30D.  |
| C13               | 19A702061P21  | Ceramic: 15 pF ±5%, 50 VDCW, temp coef 0 ±30 PF  |
| C14               | 19A702061P29  | Ceramic: 22 pF ±5%, 50 VDCW, temp coef 0 ±30 PF  |
|                   |               |  |

| SYMBOL | GE PART NO.   | DESCRIPTION   |
|--------|---------------|---|
| C15    | 19A702061P33  | Ceramic: 27 pF ±5%, 50 VDCW, temp coef 0 ±30 PPM  |
| C16    | 19A702061P23  | Ceramic: 16 pF <u>+</u> 5%, 50 VDCW, temp coef 0 <u>+</u> 30 PPM                                |
| C19    | 19A702061P61  | Ceramic: 100 pF ±5%, 50 VDCW, temp coef 0<br>±30 PPM. (Used in G1 - G3).                        |
| C19    | 19A702061P53  | Ceramic: 68 pF ±5%, 50 VDCW, temp coef 0<br>±30 PPM. (Used in G4).                              |
| C19    | 19A702061P65  | Ceramic: 150 pF ±5%, 50 VDCW, temp coef 0<br>±30 PPM. (Used in G5).                             |
| C20    | 19A702061P77  | Ceramic: 470 pF <u>+</u> 5%, 50 VDCW, temp coef 0<br><u>+</u> 30 PPM.                           |
| C21    | 19A700226P50  | Ceramic: 39 pF ±5%, 100 VDCW, temp coef 0<br>-750 PPM. (Used in G1-G3, G5).                     |
| C21    | 19A700227P50  | Ceramic: 39 pF ±5%, 100 VDCW, temp coef 0<br>-1500 PPM. (Used in G4).                           |
| C22    | 19A700229P68  | Ceramic: 120 pF ±5%, 100 VDCW, temp coef 0 -3300 PPM. (Used in G5).                             |
| C22    | 19A700228P59  | Ceramic: 68 pF ±5%, 100 VDCW, temp coef 0   |
| C22    | 19A700228P68  | -2200 PPM. (Used in G1-G3).  Ceramic: 120 pF ±5%, 50 VDCW, temp coef 0 -2200 PPM. (Used in G4). |
| C23    | 19A702061P29  | Ceramic: 22 pF +5%, 50 VDCW, temp coef 0  |
| C23    | 19A702061P21  | ±30 PPM. (Used In G1).  Ceramic: 15 pF ±5%, 50 VDCW, temp coef 0                                |
| C23    | 19A702061P35  | +30 PPM. (Used In G2 & G3).  Ceramic: 30 pF +5%, 50 VDCW, temp coef 0                           |
|        |               | ±30 PPM. (Used in G4).  |
| C23    | 19A702061P31  | Ceramic: 24 pF ±5%, 50 VDCW, temp coef 0<br>±30 PPM. (Used in G5).                              |
| C24    | 19A702061P907 | Ceramic: 3.3 pF ±.25 pF, 50 VDCW, temp coef 0<br>±120 PPM. (Used in G1).                        |
| C24    | 19A702061P909 | Ceramic: 4.7 pF ±.25 pF, 50 VDCW, temp coef 0<br>±60 PPM. (Used in G2-G5).                      |
| C25    | 19A702168P1   | Variable, ceramic: 2 to 7 pF, 100 VDCW; sim to JFD DV2SN7A.                                     |
| C26    | 19A702061P902 | Ceramic: 1.2 pF ±.25 pF, 50 VDCW, 0 ±250 PPM.   |
| C27    | 19A702061P21  | Ceramic: 15 pF ±5%, 50 VDCW, temp coef 0<br>±30 PPM. (Used in G1).                              |
| C27    | 19A702061P17  | Ceramic: 12 pF ±5%, 50 VDCW, temp coef 0<br>±30 PPM. (Used in G2).                              |
| C27    | 19A702061P19  | Ceramic: 13 pF ±5%, 50 VDCW, temp coef 0<br>±30 PPM. (Used in G3).                              |
| C27    | 19A702061P29  | Ceramic: 22 pF ±5%, 50 VDCW, temp coef 0<br>±30 PPM. (Used in G4).                              |
| C27    | 19A702061P25  | Ceramic: 18 pF ±5%, 50 VDCW, temp coef 0<br>±30 PPM. (Used in G5).                              |
| C28    | 19A702061P13  | Ceramic: 10 pF ±5%, 50 VDCW, temp coef 0 ±30 PPM  |
| C29    | 19A702061P69  | Ceramic: 220 pF ±5%, 50 VDCW, temp coef 0 ±30 PPM.  |
| C30    | 19A702061P906 | Ceramic: 2.7 pF +.25 pF, 50 VDCW, temp coef 0 +120 PPM. (Used in G1 & G5).                      |
| C30    | 19A702061P904 | Ceramic: 1.8 pF ±.25 pF, 50 VDCW, temp coef 0<br>±250 PPM. (Used in G2 & G3).                   |
| C30    | 19A702061P907 | Ceramic: 3.3 pF ±.25 pF, 50 VDCW, temp coef 0 ±120 PPM. (Used in G4).                           |
| C31    | 19A702061P69  | Ceramic: 220 pF ±5%, 50 VDCW, temp coef 0   |
| C32    | 19A702061P907 | ±30 PPM.  Ceramic: 3.3 pF ±.25 pF, 50 VDCW, temp coef 0   |
| C32    | 19A702061P906 | +120 PPM. (Used in G1).  Ceramic: 2.7 pF +.25 pF, 50 VDCW, temp coef 0                          |
| C32    | 19A702236P16  | ±120 PPM. (Used in G2 & G3).  Ceramic: 4.3 pF ±.25 pF, 50 VDCW, temp coef 0                     |
| C32    | 19A702061P908 | +30 PPM. (Used in G4).  Ceramic: 3.9 pF +.25 pF, 50 VDCW, temp coef 0                           |
|        |               | +120 PPM. (Used in G5).   |
| C33    | 19A702236P1   | Ceramic: 0.5 pF ±.1 pF, 50 VDCW, temp coef 0 ±30 PPM.   |
| C34    | 19A702061P903 | Ceramic: 1.5 pF ±.25 pF, 50 VDCW, temp coef 0 ±250 PPM.   |
| C35    | 19A702052P10  | Ceramic: 4700 pF ±10%, 50 VDCW.   |
|        |               |   |
|        |               |   |
| C35    | 19A702052P10  |   |

| SYMBOL             | GE PART NO.                    | DESCRIPTION  |
|--------------------|--------------------------------|--|
| C36                | 19A702061P37                   | Ceramic: 33 pF ±5%, 50 VDCW, temp coef 0 ±30 PPM   |
| C37                | 19A702061P61                   | Ceramic: 100 pF <u>+</u> 5%, 50 VDCW, temp coef 0<br><u>+</u> 30 PPM.  |
| C38<br>thru<br>C40 | 19A702052P26                   | Ceramic: 0.1 uF ±10%, 50 VDCW.   |
| C41                | 19A702061P13                   | Ceramic: 10 pF ±5%, 50 VDCW, temp coef 0 ±30 PPM   |
| C42                | 19A702061P61                   | Ceramic: 100 pF ±5%, 50 VDCW, temp coef 0 ±30 PPM.   |
| C43                | 19B800755P4                    | Electrolytic: 10 uF ±20%, 16 VDCW.   |
| C44                | 19A702052P28                   | Ceramic: 0.022 uF +10%, 50 VDCW.   |
| C45<br>C46         | 19A702052P105<br>19A702052P110 | Ceramic: 1000 pF ±5%, 50 VDCW.  Ceramic: 4700 pF ±5%, 50 VDCW.   |
| C47                | 19A702052P110                  | Ceramic: 6800 pF ±5%, 50 VDCW.   |
| C48                | 19A702052P14                   | Ceramic: 0.01 uF ±10%, 50 VDCW.  |
| C49                | 19A702052P26                   | Ceramic: 0.1 uF ±10%, 50 VDCW.   |
| C51                | 19A700003P9                    | Tantalum: 47 uF ±20%, 6.3 VDCW.  |
| C52<br>and<br>C53  | 19A702061P61                   | Ceramic: 100 pF ±5%, 50 VDCW, temp coef 0<br>±30 PPM.  |
| C54                | 19A702236P25                   | Ceramic: 10 pF ±.5 pF, 50 VDCW, temp coef 0 ±30 PPM. (Used in G1).   |
| C54                | 19A702236P23                   | Ceramic: 8.2 pF ±.25 pF, 50 VDCW, temp coef 0<br>±30 PPM. (Used in G2).  |
| C54                | 19A702236P20                   | Ceramic: 6.2 pF $\pm$ .25 pF, 50 VDCW, temp coef 0 $\pm$ 30 PPM. (Used in G3).                                 |
| C54                | 19A702236P28                   | Ceramic: 12 pF ±5%, 50 VDCW, temp coef 0<br>±30 PPM. (Used in G4 & G5).  |
| C55                | 19A702236P15                   | Ceramic: 3.9 pF ±.25 pF, 50 VDCW, temp coef 0<br>±30 PPM. (Used in G1).  |
| C55                | 19A702236P23                   | Ceramic: 8.2 pF ±.25 pF, 50 VDCW, temp coef 0<br>±30 PPM. (Used in G4).  |
| C55                | 19A702236P19                   | Ceramic: 5.6 pF ±.5 pF, 50 VDCW, temp coef 0<br>±30 PPM. (Used 1n G5).   |
| C56                | 19B800873P3                    | Variable, ceramic: 2.5 to 10 pF, 150 VDCW; sim to Johanson 9611.   |
| C57                | 19A702236P50                   | Ceramic: 100 pF ±5%, 50 VDCW, temp coef 0 ±30 PPM.   |
| C58                | 19A702236P28                   | Ceramic: 12 pF ±5%, 50 VDCW, temp coef 0<br>±30 PPM. (Used in G1).   |
| C58                | 19A702236P25                   | Ceramic: 10 pF ±.5 pF, 50 VDCW, temp coef 0 ±30 PPM. (Used in G2).   |
| C58                | 19A702236P23                   | Ceramic: 8.2 pF ±.25 pF, 50 VDCW, temp coef 0<br>±30 PPM. (Used in G3).  |
| C58                | 19A702236P30                   | Ceramic: 15 pF +5%, 50 VDCW, temp coef 0<br>+30 PPM. (Used in G4 & G5).  |
| C59                | 19A702236P40                   | Ceramic: 39 pF ±5%, 50 VDCW, temp coef 0<br>±30 PPM. (Used in G1).   |
| C59                | 19A702236P39                   | Ceramic: 36 pF ±.25 pF, 50 VDCW, temp coef 0<br>±30 PPM. (Used in G2).   |
| C59                | 19A702236P38                   | Ceramic: 33 pF ±5%, 50 VDCW, temp coef 0<br>±30 PPM. (Used in G3).   |
| C59                | 19A702236P42                   | Ceramic: 47 pF ±5%, 50 VDCW, temp coef 0<br>±30 PPM. (Used in G4).   |
| C59<br>C60         | 19A702236P41<br>19A702236P41   | Ceramic: 43 pF ±5%, 50 VDCW, temp coef 0<br>±30 PPM. (Used in G5).<br>Ceramic: 43 pF ±5%, 50 VDCW, temp coef 0 |
| C60                | 19A702236P40                   | +30 PPM. (Used in G5).  Ceramic: 39 pF +5%, 50 VDCW, temp coef 0   |
| C60                | 19A702236P38                   | ±30 PPM. (Used in G1)  Ceramic: 33 pF ±5%, 50 VDCW, temp coef 0  |
| C60                | 19A702236P39                   | ±30 PPM. (Used in G3)  Ceramic: 36 pF ±.25 pF, 50 VDCW, temp coef 0  |
| C60                | 19A702236P42                   | ±30 PPM. (Used in G2).  Ceramic: 47 pF ±5%, 50 VDCW, temp coef 0   |
|                    |                                | ±30 PPM. (Used in G4).   |
| C61<br>C63         | 19A700003P4<br>19B800873P3     | Tantalum: 1 uF ±20%, 35 VDCW.  Variable, ceramic: 2.5 to 10 pF, 150 VDCW; sim                                  |
|                    |                                | to Johanson 9611.  |

| LB | 13 | 13 | 02 |
|----|----|----|----|
|----|----|----|----|

| SYMBOL     | GE PART NO.                | DESCRIPTION   | SYMBOL       | GE PART NO.                 | DESCRIPTION   | SYMBOL          | GE PART NO.                  | DESCRIPTION   | SYMBOL            | GE PART NO.                  | DESCRIPTION  |
|------------|----------------------------|---|--------------|-----------------------------|---|-----------------|------------------------------|---|-------------------|------------------------------|--|
| C65        | 19A702236P28               | Ceramic: 12 pF ±5%, 50 VDCW, temp coef 0<br>±30 PPM. (Used in G2-G3).             | C93          | 19A702061P43                | Ceramic: 43 pF +5%, 50 VDCW, temp coef 0<br>+30 PPM. (Used in G4).                                  | D8              | 19A702015P3                  | Silicon; sim to IN458A.   | L25               | 19A700024P1                  | Coil, RF: 100 nH ±10%, 0.08 ohms DC res max, 100 v.                          |
| C65        | 19A702236P35               | Ceramic: 24 pF +5%, 50 VDCW, temp coef 0  | C94          | 194702061P25                | Ceramic: 18 pF +5%, 50 VDCW, temp coef 0  | D9              | 19A700079P1                  | Silicon; sim to BBY 31.   | L26               | 19A702474P4                  | Coil.  |
| C65        | 19A702236P34               | ±30 PPM. (Used in G4).  Ceramic: 22 pF +5%, 50 VDCW, temp coef 0                  | C94          | 19A702061P33                | $\pm 30$ PPM. (Used in G1-G3).  Ceramic: 27 pF $\pm 5\%$ , 50 VDCW, temp coef 0                     | D10             | 19A700155P1                  | Silicon; sim to Bat 18.   | L27               | 19A700024P1                  | Coil, RF: 100 nH <u>+</u> 10%, 0.08 ohms DC res max,<br>100 v.               |
| C65        | 19A702236P30               | ±30 PPM. (Used in G5).  Ceramic: 15 pF ±5%, 50 VDCW, temp coef 0                  |              |                             | ±30 PPM. (Used in G4).  |                 |                              |   | L28               | 19A700024P13                 | Coil, RF: 1.0 uH <u>+</u> 10%.   |
|            |                            | ±30 PPM. (Used in G1).  | C94          | 19A702061P29                | Ceramic: 22 pF ±5%, 50 VDCW, temp coef 0<br>±30 PPM. (Used in G5).                                  | F1              | 19A702169P9                  | Enclosed link: rated 3 amps @ 125 v; sim to<br>Littelfuse 255003.               | L29<br>and        | 19A702474P5                  | Coil.  |
| C66        | 19A702236P50               | Ceramic: 100 pF ±5%, 50 VDCW, temp coef 0 ±30 PPM.                                | C95          | 19A702061P45                | Ceramic: $47 \text{ pF} \pm 5\%$ , 50 VDCW, temp coef 0 $\pm 30 \text{ PPM}$ . (Used in G1-G3, G5). |                 |                              |   | L30<br>L31        | 19A700024P13                 | Coil, RF: 1.0 uH ±10%.   |
| C67        | 19A703324P2                | Electrolytic: 2.2 uF ±20%, 50 VDCW.   | C95          | 19A702061P49                | Ceramic: 56 pF +5%, 50 VDCW, temp coef 0<br>+30 PPM. (Used in G4).                                  | J1              | 19B801108G1                  | Connector, coax: BNC Series, 500 VRMS.  | L32               | 19A702474P1                  | Coil.  |
| C68<br>C70 | 19A702052P5<br>19A702168P2 | Ceramic: 1000 pF +10%, 50 VDCW.  Variable, cermic: 3 to 11 pF 100 VDCW, temp coef | C96          | 19A702061P906               | Ceramic: 2.7 pF ±.25 pF, 50 VDCW, temp coef 0   | J2<br>and<br>J3 | 19A703248P4                  | Contact, electrical. (Quantity 7 each).   | L33               | 19A700024P13                 | Coil, RF: 1.0 uH ±10%.   |
| C71        |                            | N450+300 PPM; sim to JFD DV2SN11C.  | C96          | 19A702061P905               | <u>+</u> 120 PPM. (Used in G1, G2, G5).  Ceramic: 2.2 pF <u>+</u> .25 pF, 50 VDCW, temp coef 0      | J4              | 19A703248P1                  | Contact, electrical. (Quantity 4).  | L34<br>and        | 19C850826P212                | Coil, RF: sim to Paul Smith SK-800-1.  |
|            | 19A702236P25               | Ceramic: 10 pF ±.5 pF, 50 VDCW, temp coef 0<br>±30 PPM. (Used in G1, G2, & G5).   | C96          | 19A702061P907               | <u>+250 PPM. (Used In G3).</u> Ceramic: 3.3 pF +.25 pF, 50 VDCW, temp coef 0                        | J5<br>and       | 19A703248P1                  | Contact, electrical.  | L35<br>L36        | 19C850826P612                | Coil, RF; sim to Paul Smith SK-800-1.  |
| C71        | 19A702236P30               | Ceramic: 15 pF $\pm$ 5%, 50 VDCW, temp coef 0 $\pm$ 30 PPM. (Used in G4).         |              |                             | ±120 PPM. (Used in G4).   | J6              |                              |   | L37               | 19C850826P312                | Coil, RF: sim to Paul Smith SK-800-1.  |
| C71        | 19A702236P23               | Ceramic: 8.2 pF $\pm$ .25 pF, 50 VDCW, temp coef 0 $\pm$ 30 PPM. (Used in G3).    | C97          | 19A702061P35                | Ceramic: 30 pF $\pm$ 5%, 50 VDCW, temp coef 0 $\pm$ 30 PPM. (Used in G1).                           | 19<br>18        | 19A703248P1<br>19A703248P4   | Contact, electrical.  | L38               | 19A700024P6                  | Coil. (Used in G1, G2)   |
| C72        | 19A702061P45               | Ceramic: 47 pF ±5%, 50 VDCW, temp coef 0 ±30 PPM                                  | C97          | 19A702061P33                | Ceramic: 27 pF ±5%, 50 VDCW, temp coef 0<br>±30 PPM. (Used in G2, G3).                              | J10             | 19A703248P1                  | Contact, electrical.  | L38               | 19A700024P5                  | Coil, RF: 220 nH ±10%. (Used in G3)  |
| C73        | 19A702061P61               | Ceramic: 100 pF ±5%, 50 VDCW, temp coef 0 ±30 PPM.                                | C97          | 19A702061P41                | Ceramic: 39 pF +5%, 50 VDCW, temp coef 0<br>+30 PPM. (Used in G4).                                  | J12<br>and      | 19A703248P1                  | Contact, electrical.  | L38               | 19A700024P9<br>19A700024P8   | Coil, RF: 470 nH ±10%. (Used in G4)  Coil, RF: 390 nH ±10%. (Used in G5)     |
| C74        | 19A702052P14               | Ceramic: 0.01 uF ±10%, 50 VDCW.   | C97          | 19A702061P39                | Ceramic: 36 pF +5%, 50 VDCW, temp coef 0  | J13             |                              |   | L39               | 19A703602G1                  | Coil, RF. Includes 19B800827P24 tuning slug.                                 |
| C75        | 19A702061P61               | Ceramic: 100 pF <u>+</u> 5%, 50 VDCW, temp coef 0 <u>+</u> 30 PPM.                | C98          | 19A700227P50                | ±30 PPM. (Used In G5).  Ceramic: 39 pF ±5%, 100 VDCW, temp coef 0                                   | L1              | 19A702472P32                 | Coil. (Used in G2, G3).   | L40               | 19A700024P13                 | Coil, RF: 1.0 uH ±10%.   |
| C76        | 19A702061P45               | Ceramic: 47 pF ±5%, 50 VDCW, temp coef 0 ±30 PPM                                  |              |                             | -1500 PPM. (Used in G1, G4).  | L1              | 19A702472P33                 | Coil. (Used in G4, G5).   | L42               | 19A703602G1                  | Coil, RF. Includes 19B800827P24 tuning slug.                                 |
| C78        | 19A702168P1                | Variable, ceramic: 2 to 7 pF, 100 VDCW; sim to JFD DV2SN7A.                       | C98          | 19A700226P50                | Ceramic: 39 pF ±5%, 100 VDCW, temp coef 0<br>-750 PPM. (Used in G2, G5).                            | L1              | 19A702472P3                  | Coil. (Used in G1).   | L43<br>L44        | 19A700024P13<br>19A702472P34 | Coil, RF: 1.0 uH ±10%. Coil. (Used in G2, G3).                               |
| C79        | 19A702061P3                | Ceramic: 1.5 pF ±0.5 pF, 50 VDCW, temp coef 0 +250 PPM.                           | C98          | 19A700228P50                | Ceramic: 39 pF ±5%, 50 VDCW, temp coef 0<br>-2200 PPM. (Used in G3).                                | L2              | 19A702472P30                 | Coil.   | L44               | 19A702472P7                  | Coil. (Used in G1, G4, G5).  |
| C80        | 19A702061P7                | Ceramic: 3.3 pF ±0.5 pF, 50 VDCW, temp coef 0                                     | C99          | 19A700229P68                | Ceramic: 120 pF ±5%, 100 VDCW, temp coef 0<br>-3300 PPM. (Used in G1, G2).                          | L3<br>L4        | 19C850826P211<br>19A702472P3 | Coil, RF: sim to Paul Smith SK-800-1.  Coil. (Used in G1, G2, G4, G5).          | L45               | 19A703161P2                  | Coil. (Used in G1, G2, G4, G5).  |
| C81        | 19A702168P1                | ±120 PPM.  Variable, ceramic: 2 to 7 pF, 100 VDCW; sim to                         | C99          | 19A700227P68                | Ceramic: 120 pF ±5%,50 VDCW, temp coef 0  | and<br>L5       | 10                           | 3577 (3564 12 57) 52) 51)   | L45               | 19A703161P1                  | Coil. (Used in G3).  |
|            |                            | JFD DV2SN7A.  | C99          | 194700228P68                | -1500 PPM. (Used in G3).  Ceramic: 120 pF ±5%, 50 VDCW, temp coef 0                                 | L4<br>and       | 19A702472P32                 | Coil. (Used in G3).   | L46<br>L47        | 19A700024P13<br>19A700024P13 | Coil, RF: 1.0 uH ±10%.   |
| C82        | 19A702061P69               | Ceramic: 220 pF ±5%, 50 VDCW, temp coef 0 ±30 PPM.                                |              |                             | -2200 PPM. (Used in G4).  | L5              | 104700004715                 | Co.41 P.F. 1 5 D.H. 1109  | L48<br>and        | 19A703602G1                  | Coil, RF. Includes 19B800827P24 tuning slug.                                 |
| C83        | 19A702052P14               | Ceramic: 0.01 uF ±10%, 50 VDCW.   | C99          | 19A700230P68                | Ceramic: 120 pF ±5%, 50 VDCW, temp coef 0<br>-4200 PPM. (Used in G5).                               | L6<br>L7        | 19A700024P15<br>19A700024P13 | Coil, RF: 1.5 uH ±10%.  Coil, RF: 1.0 uH ±10%. (Used in G1-G3).                 | L49               |                              |  |
| C84        | 19A702061P77               | Ceramic: 470 pF ±5%, 50 VDCW, temp coef 0<br>±30 PPM.                             | C100<br>C101 | 19A702052P3<br>19A702061P61 | Ceramic: 470 pF ±10%, 50 VDCW.  | and<br>L8       |                              | _   | L50               | 19A700024P13                 | Coil, RF: 1.0 uH ±10%.   |
| C85        | 19A702061P41               | Ceramic: 39 pF $\pm$ 5%, 50 VDCW, temp coef 0 $\pm$ 30 PPM. (Used in G1-G3, G5).  | and<br>C102  | 194702061961                | Ceramic: 100 pF ±5%, 50 VDCW, temp coef 0<br>±30 PPM.   | L7<br>and       | 19A700024P14                 | Coil, RF: 1.2 uH ±10%. (Used in G4, G5).  |                   |                              | TRANSISTORS  |
| C85        | 19A702061P43               | Ceramic: 43 pF +5%, 50 VDCW, temp coef 0 +30 PPM. (Used in G4).                   | C103         | 19A702236P6                 | Ceramic: 1.0 pF ±.25 pF, 50 VDCW, temp coef 0<br>+30 PPM.   | L8<br>L9        | 19A700024P11                 | Coil, RF: 680 nH +10%. (Used in G1, G2).  | Q1<br>Q2          | 19A702413P1<br>19A703795P1   | Silicon, NPN; sim to Phillips BFR92.  N Type: field effect; sim to MMBF4416. |
| C86        | 19A702061P29               | Ceramic: 22 pF +5%, 50 VDCW, temp coef 0<br>+30 PPM. (Used in G1-G3).             | C104         | 194702061P69                | Ceramic: 220 pF ±5%, 50 VDCW, temp coef 0   | L9              | 19A700024P10                 | Coil, RF: 560 nH ±10%. (Used in G3).  | Q3                | 19A700092P2                  | Silicon, NPN.  |
| C86        | 19A702061P31               | Ceramic: 24 pF ±5%, 50 VDCW, temp coef 0  | C106         | 19B800650P15                | ±30 PPM. Tantalum: 3.3 uF +20%, 10 VDCW.  | L9              | 19A700024P13                 | Coil, RF: 1.0 uH ±10%. (Used in G4).  | Q4                | 19A700236P2                  | Silicon, NPN; sim to BFS17.  |
| C87        | 19A702061P41               | +30 PPM. (Used in G4 & G5).  Ceramic: 39 pF +5%, 50 VDCW, temp coef 0             | C108         | 19A700219P18                | Ceramic: 4.7 pF ±5%, 100 VDCW, temp coef 0 PPM.   | L9              | 19A700024P12                 | Coil, RF: 820 nH ±10%. (Used in G5).  | Q5<br>Q6          | 19A700092P2<br>19A700076P2   | Silicon, NPN. Silicon, NPN.  |
|            |                            | ±30 PPM. (Used in G1).  | C108         | 19A700219P22                | (Used in G2, G3).  Ceramic: 6.8 pF ±5%, 100 VDCW, temp coef 0 PPM.                                  | L10<br>L11      | 19A702472P24<br>19A702472P26 | Coil. (Used in G1, G4, G5).   | Q7                | 19A700076F2                  | Silicon, PNP.  |
| C87        | 19A702061P37               | Ceramic: 33 pF ±5%, 50 VDCW, temp coef 0<br>±30 PPM. (Used in G2 & G3).           |              |                             | (Used in G1, G4, G5).   | L11             | 19A702472P25                 | Coil. (Used in G2 & G3).  | and<br>Q8         |                              |  |
| C87        | 19A702061P47               | Ceramic: 51 pF $\pm$ 5%, 50 VDCW, temp coef 0 $\pm$ 30 PPM. (Used in G4).         | C109         | 19A116192P14                | Ceramic: 0.1 uF ±20%, 50 VDCW; sim to Erie USCC CW20C104-M2.  | L12             | 19A700024P3                  | Coil, RF: 150 nH ±10%. (Used in G1, G4, G5).                                    | Q9                | 19A702448P1                  | Silicon, NPN; sim to 2N5945.   |
| C87        | 19A702061P43               | Ceramic: 43 pF ±5%, 50 VDCW, temp coef 0<br>±30 PPM. (Used in G5).                | C110         | 19A702236P25                | Ceramic: 10 pF $\pm$ .5 pF, 50 VDCW, temp coef 0 $\pm$ 30 PPM. (Used in G1, G2, G5).                | L12<br>L13      | 19A700024P2<br>19C850826P322 | Coil, RF: 120 nH ±10%. (Used in G2, G3).  Coil, RF: sim to Paul Smith SK-800-1. | Q10<br>Q11        | 19A701940P3<br>19A701808P1   | Silicon, NPN; sim to SRF-516. Silicon, NPN; sim to MPS 6595.                 |
| C88        | 19A702061P7                | Ceramic: 3.3 pF ±0.5 pF, 50 VDCW, temp coef 0 ±120 PPM.                           | C110         | 19A702236P30                | Ceramic: 15 pF ±5%, 50 VDCW, temp coef 0<br>±30 PPM. (Used in G4).                                  | L14             | 19C850826P221                | Coil, RF: sim to Paul Smith SK-800-1.   | Q12               | 19A700236P2                  | Silicon, NPN; sim to BFS17.  |
| C89        | 19A702061P13               | Ceramic: 10 pF +5%, 50 VDCW, temp coef 0  | C110         | 19A702236P23                | Ceramic: 8.2 pF ±.25 pF, 50 VDCW, temp coef 0<br>±30 PPM. (Used in G3).                             | L15             | 19C850826P211                | Coil, RF: sim to Paul Smith SK-800-1.   | and<br>Q13        |                              |  |
| C89        | 19A702061P12               | ±30 PPM. (Used In G1 & G2).  Ceramic: 8.2 pF ±0.5 pF, 50 VDCW, temp coef 0        |              |                             |   | L16             | 19A702213P1                  | Coil, RF: 1.0 mH ±6%; sim to TOKO 126AN-A5318HM.                                | Q14<br>and<br>Q15 | 19A700092P2                  | Silicon, NPN.  |
| C89        |                            | <u>+</u> 60 PPM. (Used in G3).  |              |                             |   | L17<br>L18      | 19A700024P13<br>19A702988P1  | Coil, RF: 1.0 uH ±10%.  | Q15               | 19A700026P1                  | Silicon, PNP.  |
|            | 19A702061P17               | Ceramic: 12 pF ±5%, 50 VDCW, temp coef 0<br>±30 PPM. (Used In G4 & G5).           | D1<br>D2     | 19A700155P1<br>19A700079P3  | Silicon; sim to Bat 18. Silicon; sim to BBY 31.   | L19             | 19A702473G1                  | Coil.   |                   |                              | RESISTORS  |
| C90<br>and | 19A702061P77               | Ceramic: 470 pF ±5%, 50 VDCW, temp coef 0<br>±30 PPM.                             | D2<br>D4     | 19A702015P1                 | Silicon; sim to BBY 31. Silicon; sim to IN458A.   | L20             | 19A702472P8                  | Coil.   | R1                | 19B800607P122                | Metal film: 1.2K ohms ±5%, 200 VDCW, 1/8 w.                                  |
| C91<br>C92 | 19A702052P14               | Ceramic: 0.01 uF ±10%, 50 VDCW.   | and<br>D5    |                             |   | L22<br>L23      | 19A700024P13<br>19A702472P3  | Coil, RF: 1.0 uH ±10%.  | R2                | 19A702585P99                 | Composition: 33K ohms ±5%, 150 VDCW, 1/8 w.                                  |
| C93        | 19A702061P41               | Ceramic: 39 pF ±5%, 50 VDCW, temp coef 0<br>±30 PPM. (Used in G1-G3, G5).         | D6<br>and    | 19A700079P3                 | Silicon; sim to BBY 31.   | L24             | 19A700024P13                 | Coil, RF: 1.0 uH ±10%.  | R3                | 19B800607P123                | Metal film: 12K ohms ±5%, 200 VDCW, 1/8 w.                                   |
|            |                            |   | D7           |                             |   |                 |                              |   |                   |                              |  |

# LB131302

| SYMBOL     | GE PART NO.                    | DESCRIPTION  | 0,000      | 05 0407 40                     | DECODIDATION  | CVP+DOI    | OF DART NO                   | DESCRIPTION  |
|------------|--------------------------------|--|------------|--------------------------------|---|------------|------------------------------|--|
| SAMBOL     | GE PART NU.                    | DESCRIPTION  | SYMBOL     | GE PART NO.                    | DESCRIPTION   | SYMBOL     | GE PART NO.                  | DESCRIPTION  |
| R4         | 19B800607P332                  | Metal film: 3.3K ohms <u>+</u> 5%, 200 VDCW, 1/8 w.                                    | R52        | 19A702289P7                    | Metal film: 22 ohms <u>+</u> 5%, 1/4 w.   | хүз        | 19A700042P3                  | Contact, electrical: sim to AMP 2-332070-2.                              |
| R5         | 19B800607P750                  | Metal film: 75 ohms <u>+</u> 5%, 200 VDCW, 1/8 w.                                      | R53        | 19A702289P7                    | Metal film: 22 ohms ±5%, 1/4 w; sim to Corning FP55.                                  | XY4<br>and | 19A115834P1                  | Contact, electrical: sim to AMP 2-330808-8.                              |
| R6         | 19B800607P152                  | Metal film: 1.5K ohms ±5%, 200 VDCW, 1/8 w.  | R53        | 19B800607P562                  | Metal film: 5.6K ohms <u>+</u> 5%, 200 VDCW, 1/8 w.                                   | XY5        |                              |  |
| R7<br>R8   | 19B800607P750<br>19B800607P102 | Metal film: 75 ohms ±5%, 200 VDCW, 1/8 w.  | R54        | 19A702585P63                   | Composition: 1K ohms ±5%, 150 VDCW, 1/8 w.  |            |                              |  |
| and<br>R9  | 1988006079102                  | Metal film: 1K ohms ±5%, 200 VDCW, 1/8 w.  | R55        | 19B800607P103                  | Metal film: 10K ohms <u>+</u> 5%, 200 VDCW, 1/8 w.                                    | Z1         | 19A702522G11                 | Crystal pair. (Includes 22).   |
| R10        | 19B800607P121                  | Metal film: 120 ohms +5%, 200 VDCW, 1/8 w.   | R56        | 19A702289P11                   | Metal film: 47 ohms ±5%, 1/4 w; sim to Corning  | Z2         | 10170017171                  | (Part of Z1).  Bandpass filter: 455 +1.5 kHz; sim to Murata              |
|            | 100000011121                   | (Used in G1-G3).   | R57        | 19A702585P87                   | FP55.  Composition: 10K ohms ±5%, 150 VDCW, 1/8 w.                                    | Z3         | 19A702171P1                  | CFU455D2.  |
| R10        | 19B800607P181                  | Metal film: 180 ohms <u>+</u> 5%, 200 VDCW, 1/8 w. (Used in G4, G5).                   | R58        | 19A702585P87<br>19A702585P63   | Composition: 1K ohms ±5%, 150 VDCW, 1/8 w.  |            |                              | MISCELLANEOUS  |
| R11        | 19A702585P41                   | Composition: 120 ohms ±5%, 150 VDCW. (Used in  | R59        | 19B800607P560                  | Metal film: 56 ohms ±5%, 200 VDCW, 1/8 w.   |            | 19A702471P2                  | Crystal pad. (Used in Z1 & Z2).  |
|            |                                | G1-G3).  | R60        | 19B800607F102                  | Metal film: 1K ohms ±5%, 200 VDCW, 1/8 w.   |            | 19A134793P1805               | Screw, thread forming: No. 1-64 x 7/32.                                  |
| R11        | 19A702585P45                   | Composition: 180 ohms $\pm 5\%$ , 150 VDCW, 1/8 w. (Used in G4, G5).                   | R61        | 19B800607P103                  | Metal film: 10K ohms ±5%, 200 VDCW, 1/8 w.  |            |                              | (Secures J1 mounting).   |
| R12        | 19B800607P822                  | Metal film: 8.2K ohms <u>+</u> 5%, 200 VDCW, 1/8 w.                                    | R62        | 19B800607P222                  | Metal film: 2.2K ohms +5%, 200 VDCW, 1/8 w.   |            | 19A702945P1                  | Shield.  |
| R13        | 19B800607P562                  | Metal film: 5.6K ohms <u>+</u> 5%, 200 VDCW, 1/8 w.                                    | R63        | 19B800607P331                  | Metal film: 330 ohms ±5%, 200 VDCW, 1/8 w.  |            | 19D900639G2                  | Battery Pack. 7.5 volt   |
| R14        | 19B800607P750                  | Metal film: 75 ohms <u>+</u> 5%, 200 VDCW, 1/8 w.                                      | R64        | 19B800607P123                  | Metal film: 12K ohms ±5%, 200 VDCW, 1/8 w.  |            | 19D900639G3                  | Battery Pack. 10 Volt.   |
| R15        | 19B800607P561                  | Metal film: 560 ohms ±5%, 200 VDCW, 1/8 w.   | R65        | 19A702585P81                   | Composition: 5.6K ohms <u>+</u> 5%, 150 VDCW, 1/8 w.                                  |            |                              |  |
| R15        | 19B800607P391                  | (Used in G1-G3).   | R66        | 19B800607P102                  | Metal film: 1K ohms <u>+</u> 5%, 200 VDCW, 1/8 w.                                     |            | ļ                            | ASSOCIATED PARTS   |
| KIS        | 1988006072391                  | Metal film: 390 ohms ±5%, 200 VDCW, 1/8 w. (Used in G4, G5).                           | R67        | 19B800607P223                  | Metal film: 22K ohms <u>+</u> 5%, 200 VDCW, 1/8 w.                                    |            |                              |  |
| R16        | 19B800607P104                  | Metal film: 100K ohms <u>+</u> 5%, 200 VDCW, 1/8 w.                                    | R68        | 19B800607P151                  | Metal film: 150 ohms <u>+</u> 5%, 200 VDCW, 1/8 w.                                    |            |                              | NOTE: when reordering specify GE part number and exact frequency needed. |
| R17        | 19A702585P89                   | Composition: 12K ohms ±5%, 150 VDCW, 1/8 w.  | R69        | 19B800751P16                   | Variable, solid carbon: 100K ohms ±25%, 0.05 w;                                       |            |                              | exact frequency needed.  Fx = Fo - 21.4                                  |
| R18        | 19B800607P750                  | Metal film: 75 ohms <u>+</u> 5%, 200 VDCW, 1/8 w.                                      |            | 10000000000151                 | sim to ALSP H0651A.   | ļ          |                              | 9  |
| R19        | 19B800607P101                  | Metal film: 100 ohms ±5%, 200 VDCW, 1/8 w.   | R70        | 19B800607P151                  | Metal film: 150 ohms ±5%, 200 VDCW, 1/8 w.  | Y1         | 19A702375G2                  | Quartz.  |
| R20        | 19B800607P102                  | Metal film: 1K ohms <u>+</u> 5%, 200 VDCW, 1/8 w.                                      | R71<br>R72 | 19B800607P223<br>19B800607P102 | Metal film: 22K ohms ±5%, 200 VDCW, 1/8 w.  Metal film: 1K ohms +5%, 200 VDCW, 1/8 w. | and<br>Y2  |                              | Fx = Fo  |
| R21        | 19B800607P273                  | Metal film: 27K ohms ±5%, 200 VDCW, 1/8 w.   | R72        | 19B80077102                    | Variable, solid carbon: 100K ohms ±25%, 0.05 w;                                       |            |                              | 1  |
| R22        | 19B800607P103                  | Metal film: 10K ohms ±5%, 200 VDCW, 1/8 w.   | R73        | 198800737710                   | sim to ALSP H0651A.   | <b>ү</b> 3 | 19A702284G3                  | Quartz: 20945.000 kHz  |
| R23        | 19A702585P85                   | Composition: 8.2K ohms ±5%, 150 VDCW, 1/8 w.   | R74        | 19A702585P71                   | Composition: 2.2K ohms ±5%, 150 VDCW, 1/8 w.  | Y4<br>and  | 19A702375G1                  | Quartz.  |
| R24        | 19B800607P104                  | Metal film: 100K ohms ±5%, 200 VDCW, 1/8 w.  | R77        | 19B800607P223                  | Metal film: 22K ohms ±5%, 200 VDCW, 1/8 w. (Used in G1-G3).                           | Y5         |                              |  |
| R25<br>and | 19B800607P222                  | Metal film: 2.2K ohms ±5%, 200 VDCW, 1/8 w.  | R77        | 19B800607P183                  | Metal film: 18K ohms +5%, 200 VDCW, 1/8 w.  |            |                              | MISCELLANEOUS  |
| R26        |                                | N  |            |                                | (Used in G4, G5).   |            | 19B800886P3                  | Whip antenna. (403-470 MHz).   |
| R27<br>R28 | 19B800607P473<br>19B800607P223 | Metal film: 47K ohms ±5%, 200 VDCW, 1/8 w.   | R78        | 19B800607P823                  | Metal film: 82K ohms ±5%, 200 VDCW, 1/8 w. (Used in G4, G5).                          |            | 19B800886P4                  | Whip antenna. (470-494 MHz).   |
| R29        | 19B800607P223                  | Metal film: 22K ohms ±5%, 200 VDCW, 1/8 w.  Metal film: 15K ohms ±5%, 200 VDCW, 1/8 w. | R78        | 19B800607P683                  | Metal film: 68K ohms ±5%, 200 VDCW, 1/8 w.  |            | 19B800886P5                  | Whip antenna. (489-512 MHz).   |
| R30        | 19B800607P563                  | Metal film: 56K ohms ±5%, 200 VDCW, 1/8 w.   | , nea      |                                | (Used in G1-G3).  Metal film: 47K ohms +5%, 200 VDCW, 1/8 w.                          |            | 19B800763P11                 | Helical antenna (403-425 MHz).  Helical antenna (420-450 MHz).           |
| R31        | 19B800607P682                  | Metal film: 6.8K ohms +5%, 200 VDCW, 1/8 w.  | R79        | 19B800607P473                  | Metal film: 47k onms ±5%, 200 vbcw, 1/8 w. (Used in G1-G3).                           |            | 19B800763P12<br>19B800763P13 | Helical antenna (450-470 MHz).   |
| R32        | 19B800762P1                    | Variable, carbon film: 5K ohms +20%, 150 VDCW,   | R79        | 19B800607P273                  | Metal film: 27K ohms ±5%, 200 VDCW, 1/8 w. (Used in G4, G5).                          |            | 19B800763P14                 | Helical antenna (470-494 MHz).   |
|            |                                | .1 w; sim to TOCOS RPR124.   | R80        | 19B800607P823                  | Metal film: 82K ohms ±5%, 200 VDCW, 1/8 w.  |            | 19B800763P15                 | Helical antenna (489-512 MHz).   |
| R34<br>R35 | 19B800607P563<br>19B800607P823 | Metal film: 56K ohms ±5%, 200 VDCW, 1/8 w.  Metal film: 82K ohms +5%, 200 VDCW, 1/8 w. |            |                                | (Used in G1-G3).  |            |                              |  |
| R36        | 19B800607P823                  | Metal film: 1.5K ohms ±5%, 200 VDCW, 1/8 w.  | R80        | 19B800607P104                  | Metal film: 100K ohms $\pm 5\%$ , 200 VDCW, 1/8 w. (Used in G4, G5).                  |            |                              |  |
| R37        | 19B800607P821                  | Metal film: 820 ohms ±5%, 200 VDCW, 1/8 w.   | R81        | 19B800607P123                  | Metal film: 12K ohms ±5%, 200 VDCW, 1/8 w.  |            |                              |  |
| R38        | 1886000077821                  | (Part of S1).  | R82        | 19B800607P183                  | Metal film: 18K ohms ±5%, 200 VDCW, 1/8 w.  |            |                              |  |
| R40        | 19B800779P10                   | Variable: 10K ohms +25%, 100 VDCW, .3 watt.  | R83        | 19B800607P683                  | Metal film: 68K ohms ±5%, 200 VDCW, 1/8 w.  |            |                              |  |
| R41        | 19B800607P471                  | Metal film: 470 ohms ±5%, 200 VDCW, 1/8 w.   |            |                                |   |            |                              |  |
| R42        | 19A702585P55                   | Composition: 470 ohms ±5%, 150 VDCW, 1/8 w.  | S1         | 19B800762P3                    | Variable, carbon film: 10K ohms ±20%, 150 VDCW,                                       |            |                              |  |
| R43        | 19A702585P59                   | Composition: 680 ohms ±5%, 150 VDCW, 1/8 w.  |            | 10000102F3                     | .1 w; sim to TOCOS PRP124865.   |            |                              |  |
| R44        | 19A702289P4                    | Metal film: 10 ohms ±5%, 1/4 w; sim to Corning   | S2         | 19A702244P1                    | Slide switch: DPDT, contact rating 1 mA @ 10 VDC; sim to Alps SSS02200.               |            |                              |  |
| R45        | 19B800607P101                  | FP55.  Metal film: 100 ohms +5%, 200 VDCW, 1/8 w.                                      |            |                                |   |            |                              |  |
| R47        | 19B800607P101                  | Metal film: 10 ohms ±5%, 200 VDCW, 1/8 w.  Metal film: 10 ohms ±5%, 200 VDCW, 1/8 w.   |            | 104701700                      | INTEGRATED CIRCUITS   |            |                              |  |
| R47        | 19A702585P39                   | Composition: 100 ohms ±5%, 200 VDCW, 1/8 w.  | U1         | 19A701780P1                    | Linear: IF AMPLIFIER AND DETECTOR.  |            |                              |  |
| R51        | 19B800607P103                  | Metal film: 10K ohms ±5%, 200 VDCW, 1/8 w.   | U2         | 19A702536P2                    | Linear. POSITIVE VOLTAGE REGULATOR; sim to LM2931T.                                   |            |                              |  |
| """        | 1.2.3.00                       |  |            |                                |   |            | 1                            |  |
|            |                                |  | VV.        | 19A115834P1                    |   |            |                              |  |
|            |                                |  | XY1<br>and | 19M113834P1                    | Contact, electrical: sim to AMP 2-330808-8.   |            |                              |  |
|            |                                |  | XY2        |                                |   |            |                              |  |
|            |                                |  |            |                                |   |            |                              |  |
|            |                                |  |            |                                |   |            |                              |  |
|            |                                |  |            |                                |   |            |                              |  |
|            |                                |  |            |                                |   |            |                              |  |
|            |                                |  |            |                                |   |            |                              |  |
| L          |                                | L  | L          | <b>.</b>                       |   |            |                              | <u> </u>   |

DESCRIPTION

----- RESISTORS -----

Silicon, PNP.

Silicon, NPN.

P type, field effect.

# PARTS LIST

FRONT COVER
19D900647G1 STANDARD
19D900647G2 LICENSEE
19D900647G4 CGE OPTION
ISSUE 3

### PARTS LIST

HARDWARE KIT 19A702379G1 SINGLE/MULTI FREQ 19A702379G2 UHF 19A702379G3 HIGH BAND ISSUE 3

# PARTS LIST

SYMBOL

Q10

GE PART NO.

19A700059P2

19A700076P2

19A702760P1

AUDIO BOARD 19D901123G1 STANDARD 19D901123G2 DTMF ISSUE 1

|           |              |  |          |                 |  |            |               |   | 1          |               | RESISTORS   |
|-----------|--------------|--|----------|-----------------|--|------------|---------------|---|------------|---------------|---|
|           |              | r  |          |                 |  |            | · · ·         |   | R1         | 19B800607P333 | Metal film: 33K ohms ±5%, 200 VDCW, 1/8 w.                |
| SYMBOL    | GE PART NO.  | DESCRIPTION  | SYMBOL   | GE PART NO.     | DESCRIPTION  | SYMBOL     | GE PART NO.   | DESCRIPTION   | R2         | 19B800607P683 | Metal film: 68K ohms ±5%, 200 VDCW, 1/8 w.                |
| STWIDGE   | GETARTING.   | DESCRIPTION  | 01111502 | 02 1 11111 1101 | DECORN TION  |            |               |   | R3         | 19B800607P393 | Metal film: 39K ohms ±5%, 200 VDCW, 1/8 w.                |
|           |              |  |          |                 |  |            |               |   | R4         | 19B800607P333 | Metal film: 33K ohms <u>+</u> 5%, 200 VDCW, 1/8 w.        |
|           | ļ            |  |          |                 | 1  |            |               |   | R5         | 19B800607P473 | Metal film: 47K ohms $\pm 5\%$ , 200 VDCW, 1/8 w.         |
| B1        | 19A134460P1  | Loudspeaker, permanent magnet: 2 inches, 8 ohms                                    |          | 19A702471P3     | Crystal pad. (Used with Y3).   | C1         | 19A702052P120 | Ceramic: 0.033 uF ±5%, 50 VDCW.                                     | and<br>R6  |               |   |
| В         | 198134400F1  | +10%, coil imp., 450 +100 Hz resonance, 500 mW;<br>sim to Pioneer A50AP13-01F.     | j        | 19A702471P2     | Crystal pad. (Used with Y1, Y2, Y4, Y5).                                       | C2<br>and  | 19A702052P112 | Ceramic: 6800 pF ±5%, 50 VDCW.                                      | R7         | 19B800607P153 | Metal film: 15K ohms $\pm 5\%$ , 200 VDCW, 1/8 w.         |
|           |              | <u> </u>   |          | 19A702332P1     | Nut, slotted: M7 x .75. (Secures R32 & S1).                                    | C3         |               |   | R8         | 19B800607P821 | Metal film: 820 ohms <u>+</u> 5%, 200 VDCW, 1/8 w.        |
| B2        | 19J706041P1  | Microphone cartridge: 200-850 ohms output imp., 1.5 to 10 VDC; sim to Primo EM-60. |          | 19B800849P1     | Washer, rectangular. (Located between ON-OFF                                   | C4         | 19A702052P128 | Ceramic: 0.022 uF ±5%, 50 VDCW.                                     | R9         | 19B800607P153 | Metal film: 15K ohms ±5%, 200 VDCW, 1/8 w.                |
|           |              |  | 1        |                 | switch and housing).   | C5         | 19A702052P12  | Ceramic: 6800 pF ±10%, 50 VDCW.                                     | R10        | 19B800607P180 | Metal film: 18 ohms ±5%, 200 VDCW, 1/8 w.                 |
| 1         |              |  |          | 19A702314P2     | Knurled nut. (Secures J11).  | C6         | 19A702844P1   | Tantalum: 22 uF <u>+</u> 20%, 6.3 VDCW.                             | R11        | 19B800607P104 | Metal film: 100K ohms ±5%, 200 VDCW, 1/8 w.               |
| C1<br>and | 19A700232P64 | Ceramic: 100 pF ±10%, 100 VDCW, -5600 PPM temp coef.                               |          | 19A703007P212   | Machine screw, Torx drive: M2.545 x 12. (Secures rear cover below nameplates). | C7         | 19A702052P10  | Ceramic: 4700 pF ±10%, 50 VDCW.                                     | R13        | 19A702289P1   | Metal film: 1 ohms ±5%, 1/4 w; sim to Corning             |
| C2        |              |  |          |                 | 1 '  | С8         | 19A702052P4   | Ceramic: 680 pF ±10%, 50 VDCW.                                      | R13        | 19470220971   | PL55.   |
| СЗ        | 19B800650P13 | Tantalum: 1 uF -20+40%, 10 VDCW.   |          | 19A702362P208   | Machine screw, Torx drive: M2.545 x 8. (Secures rear cover at top).            | C9         | 19A702052P26  | Ceramic: 0.1 uF ±10%, 50 VDC#.                                      | R14        | 19B800607P471 | Metal film: 470 ohms ±5%, 200 VDCW, 1/8 w.                |
|           |              | PLUGS  | 1        | 19B800859P1     | Knob, push on.   | C10        | 19B800755P7   | Electrolytic: 100 uF ±20%, 10 VDCW.                                 | R15        | 19B800607P472 | Metal film: 4.7K ohms ±5%, 200 VDCW, 1/8 w.               |
|           |              |  |          | 19A702364P103   | Machine screw, Torx drive: M24 x 3. (Secures                                   | C11        | 19B800755P4   | Electrolytic: 10 uF ±20%, 16 VDCW.                                  | R16        | 19B800607P183 | Metal film: 18K ohms ±5%, 200 VDCW, 1/8 w.                |
| P4        | 1            | Connector. Includes:   | I        |                 | option cover).   |            | 19A702052P26  | <u>-</u>  | R17        | 19B800607P683 | Metal film: 68K ohms ±5%, 200 VDCW, 1/8 w.                |
|           | 19A702405P4  | Shell.   |          | 19A700032P1     | Lockwasher, internal tooth: No. 2. (Secures option cover).                     | C12<br>and | 19A 702052P26 | Ceramic: 0.1 uF ±10%, 50 VDCW.                                      | R18        | 19B800607P473 | Metal film: 47K ohms ±5%, 200 VDCW, 1/8 w.                |
|           | 19A702405P28 | Contact, electrical.   |          | 10000000000     |  | C13        |               |   | 1          | 19B800607P562 | Metal film: 5.6K ohms ±5%, 200 VDCW, 1/8 w.               |
| W1        | 19B800860G1  | Cable assembly. (Includes P4).   |          | 19D900667P1     | Option Cover.  | C14        | 19A703324P1   | Electrolytic: 22 uF ±20%, 16 VDCW.                                  | R19        | l .           | <del>-</del>  |
|           |              | MISCELLANEOUS  |          |                 |  | C15        | 19A702052P107 | Ceramic: 2200 pF ±5%, 50 VDCW.                                      | R20        | 19B800607P183 | Metal film: 18K ohms ±5%, 200 VDCW, 1/8 w.                |
|           | 19A702396P1  | Nameplate. (GENERAL ELECTRIC).   |          |                 |  | C16        | 19A700003P4   | Tantalum: 1 uF ±20%, 35 VDCW.                                       | R21        | 19B800607P472 | Metal film: 4.7K ohms ±5%, 200 VDCW, 1/8 w.               |
|           | 19470239621  | Nameplate. (GENERAL EDECITE).  |          |                 |  | C17        | 19A702061P61  | Ceramic: 100 pF <u>+</u> 5%, 50 VDCW, temp coef 0<br>+30 PPM.       | R22        | 19B800607P331 | Metal film: 330 ohms ±5%, 200 VDCW, 1/8 w.                |
| ł         |              |  | 1        |                 |  | 212        | 10450005005   | -   | R23        | 19B800607P821 | Metal film: 820 ohms ±5%, 200 VDCW, 1/8 w.                |
| 1         | İ            |  |          |                 |  | C18        | 19A702052P5   | Ceramic: 1000 pF ±10%, 50 VDCW.                                     | R24        | 19B800607P104 | Metal film: 100K ohms ±5%, 200 VDCW, 1/8 w.               |
|           |              |  |          |                 |  | C19        | 19B800755P4   | Electrolytic: 10 uF ±20%, 16 VDCW.                                  | R25        | 19B800607P473 | Metal film: 47K ohms ±5%, 200 VDCW, 1/8 w.                |
|           |              |  |          | ţ               |  | C20        | 19A702052P122 | Ceramic: 0.047 uF ±5%, 50 VDCW.                                     | R26        | 19B800607P823 | Metal film: 82K ohms ±5%, 200 VDCW, 1/8 w.                |
|           |              |  |          |                 |  | C21        | 19A702052P110 | Ceramic: 4700 pF ±5%, 50 VDCW.                                      | R27        | 19B800607P473 | Metal film: 47K ohms <u>+</u> 5%, 200 VDCW, 1/8 w.        |
|           |              |  | i i      |                 |  | C22<br>and | 19A702052P122 | Ceramic: 0.047 uF ±5%, 50 VDCW.                                     | R28        | 19B800607P224 | Metal film: 220K ohms ±5%, 200 VDCW, 1/8 w.               |
|           |              |  |          |                 |  | C23        |               |   | R29        | 19B800607P823 | Metal film: 82K ohms ±5%, 200 VDCW, 1/8 w.                |
| 1         |              |  |          |                 |  | C24        | 19A702061P61  | Ceramic: 100 pF ±5%, 50 VDCW, temp coef 0 ±30 PPM.                  | R30        | 19B800607P334 | Metal film: 330K ohms ±5%, 200 VDCW, 1/8 w.               |
|           |              |  |          |                 |  |            |               | -   | R31        | 19B800607P103 | Metal film: 10K ohms ±5%, 200 VDCW, 1/8 w.                |
|           |              |  |          |                 |  | C25        | 19A702052P106 | Ceramic: 1500 pF ±5%, 50 VDCW.                                      | R32        | 19B800607P223 | Metal film: 22K ohms ±5%, 200 VDCW. 1/8 w.                |
|           |              |  |          | İ               |  | C26        | 19B800755P2   | Electrolytic: 2.2 uF ±20%, 50 VDCW.                                 | R33        | 19B800607P183 | Metal film: 18K ohms ±5%, 200 VDCW, 1/8 w.                |
|           |              |  |          |                 |  | C27        | 19A702061P73  | Ceramic: 330 pF ±5%, 50 VDCW, temp coef 0 ±30 PPM.                  |            | ł             | <u>-</u>  |
|           | i            |  | <u> </u> |                 |  | C28        | 19A702061P61  | Ceramic: 100 pF ±5%, 50 VDCW, temp coef 0                           | R34        | 19B800607P333 | Metal film: 33K ohms ±5%, 200 VDCW, 1/8 w.                |
|           |              |  |          | l               |  |            |               | ±30 PPM.  | R35        | 19B800607P103 | Metal film: 10K ohms ±5%, 200 VDCW, 1/8 w.                |
|           |              |  |          | 1               |  | C30<br>and | 19B800755P2   | Electrolytic: 2.2 uF ±20%, 50 VDCW.                                 | R36        | 19B800607P223 | Metal film: 22K ohms ±5%, 200 VDCW, 1/8 w.                |
|           |              |  | ] ]      |                 |  | C31        |               |   | R37        | 19B800607P183 | Metal film: 18K ohms ±5%, 200 VDCW, 1/8 w.                |
|           |              |  |          | }               |  | C32        | 19A702061P61  | Ceramic: 100 pF ±5%, 50 VDCW, temp coef 0                           | R38        | 19A701828P1   | Thermistor: 3.3K ohms ±5%; sim to Philips 2322-642-63332. |
|           |              |  |          |                 |  |            |               | ±30 PPM.  | R39        | 19B800607P124 | Metal film: 120K ohms ±5%, 200 VDCW, 1/8 w.               |
|           |              |  |          |                 |  | C33        | 19A702052P26  | Ceramic: 0.1 uF ±10%, 50 VDCW.                                      | 1          | I .           | Metal film: 27K ohms ±5%, 200 VDCW, 1/8 w.                |
|           |              |  |          |                 |  |            |               | DIODES  | R40        | 19B800607P273 | <u> </u>  |
|           | 1            |  | 11       |                 |  | D1         | 19A700028P1   | Silicon, fast recovery: fwd current 75 mA,                          | R41        | 19B800607P334 | Metal film: 330K ohms ±5%, 200 VDCW, 1/8 w.               |
|           |              |  |          |                 |  | and<br>D2  |               | 75 PIV; sim to Type 1N4148.   | R42<br>and | 19B800607P473 | Metal film: 47K ohms ±5%, 200 VDCW, 1/8 w.                |
|           |              |  | 11       |                 |  | "          |               |   | R43        |               |   |
|           | 1            |  |          |                 |  |            | 104700041750  |   | R44        | 19B800607P102 | Metal film: 1K ohms ±5%, 200 VDCW, 1/8 w.                 |
|           |              |  | l i      |                 |  | P2<br>and  | 19A700041P56  | Printed wire: 7 contacts rated @ 2.5 amps; sim to Molex 22-02-2075. | R45        | 19B800607P471 | Metal film: 470 ohms ±5%, 200 VDCW, 1/8 w.                |
|           |              |  |          |                 |  | P3         |               |   |            |               |   |
|           |              |  | 1        |                 |  |            |               | TRANSISTORS   | 1          | 101705::      |   |
|           |              |  |          |                 |  | Q1         | 19A134739P2   | Silicon, NPN.   | U1         | 19A702410P1   | Linear: Audio Amplifier; sim to TBA-820M.                 |
|           |              |  |          |                 |  | Q2         | 19A700026P1   | Silicon, PNP.   |            |               | MISCELLANEOUS   |
|           |              |  |          |                 |  | Q3         | 19A700076P2   | Silicon, NPN.   |            | 19A701622P1   | Cotter pin. (Located between R15 & R19 - G2               |
|           |              | 1  |          |                 |  | thru<br>Q7 |               |   |            |               | only).  |
| 1         |              | 1  |          |                 |  |            | 1             |   |            | 19B232682P11  | Ensolite pad.   |
| 1         |              | 1  | 1        |                 | 1  | 1 1        |               |   |            | 1             |   |
|           |              |  | 11       |                 | 1  | 1 1        | 1             |   |            |               |   |
|           |              |  | 11       |                 | 1  | 1 1        |               |   |            |               |   |
|           |              |  | J L      |                 |  | J L        | <u>l</u>      |   |            | L             |   |

LB I 3 1 3 0 2

PARTS LIST

SIDE PANEL 19D900646G1 1 FREQ 19D900646G3 2 FREQ ISSUE 3

PARTS LIST

REAR COVER
19D90108761 HB HIGH POWER
19D90108762 UHF HIGH POWER
19D90108763 HB LOW POWER
19D90108764 UHF LOW POWER
ISSUE 1

SIDE PANEL '
19D901089G1 1 FREQ
19D901089G2 2 FREQ
ISSUE 1

SYMBOL GE PART NO. SYMBOL GE PART NO. SYMBOL GE PART NO. DESCRIPTION DESCRIPTION DESCRIPTION 19A703304P1 Telephone jack: rated 1/8 amp @ 125 VAC; sim to Switchcraft MDSL-280. Push switch: contacts rated 25 mA @ 9 VDC; sim to Bowmar KB3256-1D. Connector. Includes: 19B800852P1 Contact, electrical. ----- MISCELLANEOUS -----19A701728P2 Washer, non-metallic. Push switch: contacts rated 25 mA @ 9 VDC; sim to Bowmar KB3256-1D. 19B800847P1 19B800864G1 19A701488P2 Retaining ring. 19C850854P1 Slide button. Spring. ---- MISCELLANEOUS -----Contact, electrical. (Quantity 2). 19B800851P1 Insulator. 19A702461P1 Screw, thread forming: No. 0-40 x 1/4. (Secures slide button). 19A702471P6 Crystal Pad. P2 Connector. Includes: 19A703672P1 Switch stop. (G1 only). 19B800864G1 Pushbutton. 19B800852P1 Contact, electrical. 19C850854P1 Slide button. 19A701728P2 Washer, non-metallic; 19A702460P1 Contact, electrical. (Used with S1). 19A701488P2 Retaining ring. 19B232415P1 Bushing. 19B216401P5 Spring. 19A702918P1 Support, slide button. 19A702405P26 Contact, electrical: rated @ 3 amps. 19A702471P6 Crystal pad. 19A703459P1 Spacer. (Located under slide button). Option receptacle. N327P9008E Rivet, tubular. 19A702471P6 19C850861P2 Insulator, glass epoxy

\*COMPONENTS ADDED, DELETED OR CHANGED BY PRODUCTION CHANGES. \*COMPONENTS ADDED, DELETED OR CHANGED BY PRODUCTION CHANGES.

PARTS LIST

# ADDENDUM NO.1 TO LBI31302

This addendum describes Revision Letter changes that are not yet included in the publication.

# REV.A- Audio Board 19D901123G1.2

Incorporated in initial shipment.

# REV.B-Audio Board 19D901123G1.2

To improve operation. Changed printed wiring.

# REV.C-Audio Board 19D901123G1,2

To improve modulation balance on DTMF port, and to improve deviation symmetry. Changed R41, R42 and C27.

# Components are:

R41; 19B800607P224, Metal film, 220K ohms + 5%, 200 VDCW, 1/8 w. R42; 19B800607P223, Metal film, 22K ohms + 5%, 200 VDCW, 1/8 w.

C27; 19A702061P77, Ceramic, 100 pF  $\pm$  5%,  $\overline{50}$  VDCW, temp coef 0 +30 PPM.